

SURVEY & REMONUMENTATION

APR 05 1996

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| <u>Ottawa</u> <small>(County)</small> | Located In: | Corner Code # |
|--|--------------------------|---------------|
| 1. Public Land Survey | T <u>7N</u> R <u>14W</u> | <u>H-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECORDED
95 NOV 29 PM 1:46
Richard R. Rosema
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Maurice J. Rosema, in a field survey on Sept. 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-11
Original gov't cor. L.C.R.C. per Liber 1, Page 153 (1971) - over
set in 1832 by
Noah Brookfield L.C.R.C. per Liber 1, Page 817 (1972) - over
Set post
12" Beech S23°W 22 lks. L.C.R.C. per Liber 5, Page 162 (1984) - over
12" Beech N11°W 25 lks. L.C.R.C. per Liber 5, Page 246 (1986) - over

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-11
Found Cast Iron monument in monument box
Found nail in SW side P. pole N43°W 65.71'
Found nail in SW side P. pole N53°E 63.22'
Found nail in SE side P. pole S52°W 80.40'

PA. 345 OTTAWA COUNTY
PEER APPROVED 11-20-95

Richard R. Rosema
JDN

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-11
Cast Iron monument in monument box
Set nail and O.C. tag in NE side P. pole S35°E 43.25'
Set nail and O.C. tag in SE side P. pole N53°E 63.22'
Set nail and O.C. tag in SW side P. pole N43°W 65.71'
Set nail and O.C. tag in SE side P. pole S52°W 80.40'
On centerline of N-S bit. conc. road
On centerline of E-W gravel road



Signed by *Maurice J. Rosema* Date Nov. 14, 1995
Surveyor's Michigan License No. 27459

H-11 T7N, R14W

L.C.R.C. recorded in Liber 1, Page 153
- November 23, 1971
R.R. Spike in Monument box

L.C.R.C. recorded in Liber 1, 8173 ²⁷
- December 14, 1972
RR spike in C mon box
SW cor hse fnd N45°E 105.40'
32" Maple S25°E 92.95'
CP pole N50°W 65.70'

L.C.R.C. recorded in Liber 5, Page 162
- December 7, 1984
RR spike in mon box
Nail and B.C. in E side 36" Maple SSE 92.94'
Nail in NE side P pole NW 65.74'
SW cor siding of hse NE 104.94'

L.C.R.C. recorded in Liber 5, Page 246
- August 28, 1986
C.I. Monument
PP NE 63.20'
PP NW 65.70'
PP SW 80.32'
TP SE 43.45'

\$ 11.00 CORNER