

SURVEY &
REMONUMENTATION

APR 05 1996 Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	H-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
95 NOV 29 PH 1:46
Robert Carlsson
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

I, Maurice J. Rosema, in a field survey on Sept. 1, 1995
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
H-13
Original gov't cor. L.C.R.C. per Liber 1, Page 311 (1972) - over
set by
(not date of given) L.C.R.C. per Liber 5, Page 3 (1982) - over
Set H.M.P.
7" Beech N80 $\frac{1}{2}$ °E 18 lks. L.C.R.C. per Liber 6, page 152 (1991) - over
26" Pine N50°W 30 lks.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-13
Found Cast Iron monument in monument box
Found nail in P. pole NNW 54.15'
Found nail in top of wood post at tele. box NNE 60.79'
Cast Iron monument in monument box W 33.50'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11-20-95
Kudby D. Hedewald
GDR

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-13
Cast Iron Monument in monument box
Set nail and O.C. tag in W side P. pole N28°W 54.15'
Set nail and O.C. tag in W. side P. pole S30°W 65.70'
Set nail and O.C. tag in top of wood post at tele. box
Set nail and O.C. tag in N side 10" Pine N47°E 60.79'
Cast Iron monument in monument box N74°W 96.45'
On centerline of E-W bit. conc. road W 33.50'
On centerline of bit. conc. road to N



Signed by *Maurice J. Rosema* Date Nov. 14, 1995
Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

H-13 T7N, R14W

L.C.R.C. recorded in Liber 1, Page 311

- April 7, 1972

Iron in Monument Box

Nail in side T.Pole SE 41.37'

Nail in side P.Pole SSW 65.70'

SE corner hse fnd NNW 133.98'

L.C.R.C. recorded in Liber 5, Page 3

- October 15, 1982

C.I. Monument

Lite Pole NNW 54.46'

10" Catalpa WNW 73.96'

Power Pole SSW 65.74'

Blendon Cor. W 33.64'

L.C.R.C. recorded in Liber 6, Page 152

- August 22, 1991

Replaced Cast Monument

Head of 60d nail S side P.Pole N30°W 54.64'

PK to of 4"x 4" Post N40°E 60.65'

PK NW cor. Bit Parking S60°E 104.68'

16d nail E side P.Pole S30°W 65.74'

Cast Monument (N1/4 cor. Sec. 3 Blendon) Due West 33.54'

\$ 11.00 CORNER