

SURVEY & REMONUMENTATION

FEB 27 1998

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>IN</u> R <u>14W</u>	L <u>2</u>	
	T <u> </u> R <u> </u>	E <u>1/4 cor. Sec. 3</u>	
	T <u> </u> R <u> </u>		
	T <u> </u> R <u> </u>		
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>		
	S <u> </u> T <u> </u> R <u> </u>		
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>		
	S <u> </u> T <u> </u> R <u> </u>		

RECORDED

97 DEC -8 AM 11:29

Mary S. Sibley
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice J. Rosema, in a field survey on Jan. 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36

A. Description of original monument and accessories and/or subsequent restoration:

- I-2
- GLO - Mullett - 1837 LCRC per L. 5, P. 333 (1988) LCRC per L. 4, P. 24 (1980)
- post T-iron T-iron - at fc cor N and W
- 15" Ash Nail in S side fc post - W 0.30' Spk in cor. fc post - W 0.30'
- S5°W 15 lks Nail/tag in E side tw 6" Apple - N 26.42' Nail/tag in E side fc post - Se 19.8'
- 15" Beech - Nail/tag in S side 4" Apple - W 24.85' Steel fc post - S 15'
- N4°E 25 lks
- LCRC per L. 6, P. 213 (1992) - CI mon - 4" Apple - N 24.10'
- T-iron - E 54.68', fc post - W 6.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-2
- Found C.I. monument
- Found nail in E side 5" Apple - N 24.10'
- Found nail in S side wood post - W 0.35'
- Found nail in S side wood post - W 6.65'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-1-97
[Signature]

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-2
- C.I. monument
- Set nail and remon. tag in E side 5" Apple - N4°W 24.10'
- Set nail and remon. tag in S side wood post - S86°W 0.35'
- Set nail and remon. tag in S side wood post - N85°W 6.65'
- Centerline of base of steel fc post - S78°E 69.70'



\$ 9.00 CORNER
\$ 1.00 PHOTO

Signed by *[Signature]*
Surveyor's Michigan License No. 27459

Date 12/01/97