

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 18 PM 4: 54

Richard S. Chalmers
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code =#
1. Public Land Survey	T T7N R R14W	I-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J. Rosema, in a field survey on Feb. 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4		
GLO - 1832 by	L.C.R.C. recorded in Liber 5,	L.C.R.C. recorded
Noah Brookfield for	Page 33 - November 3, 1988	in Liber 4, Page
Calvin Britain D.S.	Capped 1/2" rerod no. 23517	278 - July 14, 1981
Set Post	Nail in W side 12" Ash	Steelbar #23517
7" Blk. Ash N33°E 20 lks.	Nail in W side 8" Ash	10" Ash NE 29.13'
10" Maple S10°W 16 lks.	Nail in N side 12" Ash	12" Ash SE 17.28'
	Nail in S side dead 12" Ash	7" Ash S 57.79'
		10" Ash SW 47.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4	
Found capped 1/2" rerod, replaced with 3/4" X 3' steel rod with O.C. cap	
Found nail in SE side 12" dead Ash	SE 17.33'
Found nail in W side 12" Ash	NNE 28.97'
Found nail in N side 12" Ash	WSW 47.55'


P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12/11/95

Murray D. Hedewell
M.D.H.

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4	
3/4" X 3' steel rod with O.C. cap	
Set nail and O.C. tag in SE side 12" dead Ash	S41°E 17.33'
Set nail and O.C. tag in W side 12" Ash	N35°E 28.97'
Set nail and O.C. tag in N side 12" Ash	S74°W 47.55'
Set nail and O.C. tag in W side 8" Ash	S11°W 57.71'
Centerline of E-W ditch	S 289'±



Signed by *Maurice J. Rosema* Date November 20, 1995
 Surveyor's Michigan License No. 27459