

**SURVEY &
REMONUMENTATION**

APR 05 1996 Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 DEC 12 PH 4: 53

For corners in

Ottawa

(County)

Located In:

Corner Code #

		T7N R14W	I-6	
1. Public Land Survey	T	R	_____	
	T	R	_____	
	T	R	_____	
	T	R	_____	
2. Property Controlling in Section	S	T	R	_____
	S	T	R	_____
3. Miscellaneous Property in Sec.	S	T	R	_____
	S	T	R	_____

Rhonda Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Maurice J. Rosema Oct. 11, 1994
in a field survey on _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6	GLO - 1832 by Noah Brookfield for Calvin Britain D.S. 30" W. Oak S40°W 8 lks. 20" W. Oak N20°E 36 lks.	L.C.R.C. recorded in Liber 4, Page 217 - Sept. 23, 1981 (over) L.C.R.C. recorded in Liber 5, Page 222 - Sept. 5, 1985 (over)	L.C.R.C. recorded in Liber 2, Page 653 - Oct. 9, 1974 (over)
-----	--	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6
Found C.I. mon. in gravel road 0.4' deep
Found nail in E side P pole NE 53.49'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/11/95

Rhonda Robinson
MJR

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6
C.I. mon.
Set nail and O.C. tag in E side wood post at T box S41°W 40.21'
Set nail and O.C. tag in E side P pole N33°E 53.49'
Set nail and O.C. tag in N side 20" Maple S73°W 57.81'
Set nail and O.C. tag in N side 18" Maple S53°E 54.48'
Set nail and O.C. tag in S side 30" Maple N59°E 52.25'
At centerline of gravel roads N-S-E-W



Signed by *Maurice J. Rosema* Date Nov. 20, 1995

Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

L.C.R.C. recorded in Liber 4, Page 217

- Sept. 23, 1981

C.I. mon.

36" Maple	WNW 69.72'
18" Black Cherry	SE 54.44'
P pole	NE 53.50'
Guy pole	SW 40.63'

L.C.R.C. recorded in Liber 5, Page 222

- Sept. 5, 1985

C.I. mon.

Nail in NE side 32" Maple	WNW 69.72'
Nail in E side P pole	NE 53.52'
Nail in NE side 18" W Cherry	SE 54.40'
Nail in E side Guy pole	SW 40.69'

At centerline gravel roads E-W-N-S

L.C.R.C. recorded in Liber 2, Page 653

- Oct. 9, 1974

Angle iron

36" Maple	WNW 69.73'
36" Maple	NW 36.95'
P pole	NE 53.33'
16" Maple	SW 58.39'
St. sign	SE 39.10'