

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 18 PM 4: 56

For corners in

|                                       |                            |                       |
|---------------------------------------|----------------------------|-----------------------|
| <u>Ottawa</u><br>(County)             | Located In:                | Corner Code #         |
| 1. Public Land Survey                 | T <u>T7N</u> R <u>R14W</u> | I-8                   |
|                                       | T _____ R _____            | (E $\frac{1}{4}$ cor. |
|                                       | T _____ R _____            | Sec. 22)              |
|                                       | T _____ R _____            | _____                 |
|                                       | T _____ R _____            | _____                 |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____    | _____                 |
|                                       | S _____ T _____ R _____    | _____                 |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____    | _____                 |
|                                       | S _____ T _____ R _____    | _____                 |

*Maurice J. Rosema*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Maurice J. Rosema, in a field survey on Oct. 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-8  
 GLO - 1832 by Noah Brookfield L.C.R.C. recorded in Liber \_\_\_\_\_ L.C.R.C. recorded in  
 for Calvin Britain D.S. 1, page 441 - June 9, 1972 Liber 4, Page 217 - Sept. 23,  
 10" Sugar S39°E 9 lks (over) 1981  
 10" Beech N19°W 22 lks. L.C.R.C. recorded in Liber 5, (over)  
 Page 149 - Aug. 1, 1984  
 (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8  
 Found C.I. mon. 1.7' deep with capped rerod #27459 above it, replaced rerod with 3/4" X 1' steel rod with O.C. cap  
 Found nail in NW side P pole SW 49.40'  
 Found nail in S side 18" Sassafrass W 51.57'  
 Found nail in NE side 26" Maple SE 28.34'  
 Found nail in W side 24" Maple SSE 66.16'

PA. 345 OTTAWA COUNTY  
 PEER APPROVED 12-9-96

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

*M. J. Rosema*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8  
 3/4" X 1' steel rod with O.C. cap above C.I. mon.  
 Set nail and O.C. tag in NW side P pole S69°W 39.40'  
 Set nail and O.C. tag in S side 18" Sassafrass NB84°W 51.57'  
 Set nail and O.C. tag in NE side 26" Maple S52°E 28.34'  
 Set nail and O.C. tag in W side 24" Maple S15°E 66.16'  
 On tree row to W  
 Centerline of N-S gravel road W 1'



Signed by *M. J. Rosema*  
 Surveyor's Michigan License No. 27459

Date Oct. 21, 1995

I-8, T7N, R14W

L.C.R.C. recorded in Liber 1, Page 441

- June 9, 1972

3/4" Pipe

Nail in face of 17" Maple SE 27.34'

Nail in face of Power pole SW 39.13'

Nail in face of 13" Sassafrass W 20.53'

L.C.R.C. recorded in Liber 4, Page 217

- September 23, 1981

Cast Iron Monument

Power Pole SW 39.46'

18" Sassafras W 52.18'

26" Maple SE 28.28'

24" Maple SSE 66.68'

L.C.R.C. recorded in Liber 5, Page 149

- August 1, 1984

C.I. Monument

Nail in NW side P.pole SW 39.45'

Nail in NE side 26" Maple SE 28.35'

Nail in S side 18" Sassafras W 52.24'

Nail in W side 24" Maple SSE 66.80'