

Ottawa County remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 93 DEC 15 AM 9:28

Maurice J. Rosema
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in
 Ottawa

| | | |
|---------------------------------------|--------------------------|---------------|
| (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>7N</u> R <u>14W</u> | <u>I-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

SURVEY & REMONUMENTATION

DEC 05 2000

Register of Deeds Stamp & File Number

I, Maurice J. Rosema, in a field survey on July 31, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|------|---|---|---|
| I-13 | Excel Engineering - 1974 per L.C.R.C. recorded in Liber 2, Page 501 1" iron Spike with blaze on side P. pole - NE 93.06' Face of 3" street sign - SE 30.40' P.K. nail in side T. pole - SW 46.20' | Joiner - 1981 per L.C.R.C. recorded in Liber 4, Page 104 C.I.M. P. pole - NE 77.84' T. pole - SW 46.08' 11" tree - SE 93.26' Blendon corner - W 18.35' | Prein and Newhof - 1991 per L.C.R.C. recorded in Liber 6, Page 152 C.I.M. Nail and tag in E side tw 12" Elm - N20°W 111.10' 60d S side P. pole - N45°E 93.20' P.K. in N side P. pole - N65°E 77.92' |
|------|---|---|---|


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| | | |
|------|---|--|
| I-13 | Found C.I. monument in mon. box Found Blendon corner (C.I. mon. in mon. box) - W 18.37' Found nail in top of T. box - S45°W 46.33' Found P.K. nail in NW side P. pole - N68°E 77.93' | Nail in NE side 18" Elm - S25°E 93.23' Nail in top of 6" post - S45°W 46.23' Blendon corner - W 18.37' |
|------|---|--|

I hereby accept this corner as a correct and accurate perpetuation of the position of the original section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Set O.C. remon. cap in conc. above C.I. monument in monument box
 Set nail and O.C. remon. tag in W side 19" Elm - S27°E 93.26'
 Set nail and O.C. remon. tag in E side P. pole - S15°W 140.78'
 Set nail and O.C. remon. tag in NW side P. pole - N68°E 77.93
 Set nail and O.C. remon. tag in top of T. box post - S45°W 46.33'
 Set nail and O.C. remon. tag in E side 13" quad. Elm - N15°W 111.17'
 On centerline of E-W bit. conc. road
 On centerline of gravel road to N
 Centerline of gravel road to S - W 10'



Signed by *Maurice J. Rosema* Date September 3, 1993
 Surveyor's Michigan License No. Tru-Line Surveying 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983