

Ottawa county Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**RECORDED**

96 DEC 18 PM 4:56

For corners in

<u>Ottawa</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R14W</u>	J-9
	T _____ R _____	(S $\frac{1}{4}$ cor.
	T _____ R _____	Sec. 23)
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

*D. J. ...*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Maurice J. Rosema, in a field survey on Oct. 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 J-9

GLO - 1832 by Noah Brookfield for Calvin Britain D.S. Set post 10" Beech S6°E 4 lks. 10" Beech N31°E 24 lks.	L.C.R.C. recorded in Liber 1, Page 441 - June 9, 1972 (over) L.C.R.C. recorded in Liber 2, page 521 - July 9, 1974 (over)	L.C.R.C. recorded in Liber 5, Page 199 - Feb. 20, 1985 (over) L.C.R.C. recorded in Liber 6, Page 158 - Oct. 11, 1991 (over)
--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 J-9

Found 3/4" solid iron rod in mon. box, replaced rod with 3/4" X 2' steel rod with O.C. cap  
 Found PK nail in S side P pole NE 51.63'

RA. 245 OTTAWA COUNTY  
 PEER APPROVED 12-9-96

*M.J.R.*

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 J-9

3/4" X 2' steel rod with O.C. cap in mon. box	S35°W 57.42'
Set nail and O.C. tag in E side P pole	N46°E 96.90'
Set nail and O.C. tag in N side 7" Pine	N27°W 62.43'
Set nail and O.C. tag in W side wood post at T box	N31°E 51.63'
Set nail and O.C. tag in S side P pole	N 1'
Centerline of E-W bit. conc. road	
On centerline of N-S bit. conc. road	



Signed by Maurice J. Rosema  
 Surveyor's Michigan License No. 27459

Date October 21, 1995

J-9, T7N, R14W

L.C.R.C. recorded in Liber 1, Page 441  
- June 9, 1972

Monument Box

Nail in face of Power Pole	NE 51.60'
Nail in face of Tele Pole	SW 48.00'
Nail in face of Tele Pole	NW 56.60''

L.C.R.C. recorded in Liber 2, Page 521  
- July 9, 1974

Monument Box

P.P.	NE 51.60'
Tele. pole	SW 48.00'
tele. pole	NW 56.60'

L.C.R.C. recorded in Liber 5, Page 199  
- February 20, 1985

3/4" Solid Iron in Monument box

PK in face P.pole	NE 51.69'
PK in SE side P.pole	SW 48.48'
PK in SW side post at Tele. Box	NW 62.52'

At centerline "x" Rds. N-S and E-W

L.C.R.C. recorded in Liber 6, Page 158  
- October 11, 1991

Bolt spike Monument Box

PK Nail PP	NE 52.18'
Guy Pole	SW 48.20'
Tele ped post	NW 62.58'
Gas line marker	SE 51.01'