

**SURVEY &
REMONUMENTATION**

APR 05 1996

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 DEC 12 PM 4: 51

For corners in

COMMISSION

Richard Kellman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R14W</u>	K-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Maurice J. Rosema, in a field survey on Jan. 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-3	L.C.R.C. recorded in Liber 1,
GLO - 1837 by	Page 237 - Dec. 22, 1971
John Mullett D.S.	1" Iron
Set post	Nail in SW side T pole ENE 61.8'
10" Sugar S21°W 32 lks.	Nail in W side Thornapple N 106.94'
11" Beech N5°E 27 lks.	X cut in NW end of culvert E 12.14'
	Nail in N side guard post E 18.1'
	X cut in SE end of culvert SE 42.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3
Found C.I. mon.
Found X cut in SE end of culvert E 11.75'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/11/95

Murray D. Hedewold
MDH

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3	
C.I. mon.	
Set nail and O.C. tag in W side wood post	N12°E 28.76'
Set nail and O.C. tag in side of 5" Ash	N0°W 34.70'
Set nail and O.C. tag in S side clump 4" Maple	N78°E 13.07'
Set nail and O.C. tag in SE side 7" Birch	N44°E 13.65'
X cut in SE end conc. culvert	N83°E 11.75'
In W'ly roadway ditch of Johnson Street	
On line with centerline of gravel road to E	
Centerline of gravel road to S (extended)	E 5'
Centerline of gravel road (to c/l curve)	SE 33'



Signed by Maurice J. Rosema
Surveyor's Michigan License No. 27459

Date Nov. 20, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 11
REVISED MAY 14, 11
REVISED JAN., 11