

SURVEY &  
REMONUMENTATION

APR 05 1996

Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Ottawa

	Located In:	Corner Code #	
		7N	14W
1. Public Land Survey	T ___ R ___	K-5	
	T ___ R ___		
	T ___ R ___		
	T ___ R ___		
2. Property Controlling in Section	S ___ T ___ R ___		
	S ___ T ___ R ___		
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		
	S ___ T ___ R ___		

RECORDED  
95 NOV 29 PM 1:37  
*R. J. Rosema*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Maurice J. Rosema, in a field survey on Sept. 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
K-5

Original gov't cor. set in 1832 by Noah Brookfield	L.C.R.C. per Liber 5, Page 150 (rec. Aug. 1, 1984)
20" Sugar N81°W 46 lks.	T-iron
16" Sugar S70°E 14 lks.	Nail in S side 6" Ash E 50.46'
	Nail in NW side 20" Crabapple ESE 40.90'
	Nail in NW side clump 5" Crabapple SE 13.88'
	Nail in E side 3" Oak S 25.20'
	Centerline of wood post S 1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
K-5

Replaced T-iron with 3/4" X 2' steel bar with standard O.C. remon. cap	
Found nail in NW side 5" Crabapple clump	S46°E 13.86'
Found nail in E side 3" Oak	S8°W 25.18'
Center of wood fence post	S 0.67'

PA. 345 OTTAWA COUNTY  
PEER APPROVED 11/20/95

*M. J. Rosema*  
*MJR*

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K-5

3/4" X 2' steel bar with standard O.C. remon. cap	
Set nail and O.C. tag in NW side 5" Crabapple clump	S46°E 13.86'
Set nail and O.C. tag in W side 7" Oak	S8°W 29.33'
Set nail and O.C. tag in E side 3" Oak	S8°W 25.18'
Set nail and O.C. tag in W side 11" tree	S30°E 43.41'
Set nail and O.C. tag in S side 10" Ash	S78°E 50.55'
Tree row to S	W 1'
Tree row to E	N 1'



Signed by *M. J. Rosema*  
Surveyor's Michigan License No. 27459

Date Nov. 14, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28  
REVISED MAY 14  
REVISED JAN.