

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED  
94 DEC 15 AM 11:53

*Edyette Williams*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

SURVEY &  
REMONUMENTATION

DEC 05 2000

SECTION  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Maurice J.

Rosema

Oct. 11

94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-7  
 GLO - 1832 by VanKooten - 1972 per L.C.R.C. Joiner - 1981 per L.C.R.C.  
 Noah Brookfield for rec. in L. 1, P. 769 (over) rec. in L. 4, P. 288 (over)  
 Calvin Britain D.S.  
 20" Beech - N37°E .32 ch. Bonnema - 1981 per L.C.R.C. Rosema - 1985 per L.C.R.C.  
 16' Sugar - S63°W .21 ch. rec. in L. 4, P. 214 (over) rec. in L. 5, P. 201 (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-7  
 Found railroad spike in mon. box (above a 2nd mon. box with cover), set 3/4" x 1' rod with std. remon cap  
 Found nail in NW. side 16" Catalpa - N84°E 33.46'  
 Found nail in NE. side Power pole - N28°W 54.88'  
 Found spike in S. side Power pole - N89°E 60.03'

PEER APPROVED 12/12/94

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7  
 3/4" x 1' rod with std. remon. cap in mon. box  
 Set nail and remon. tag in Railroad tie - S84°E 33.92'  
 Set nail and remon. tag in NW. side 16" Catalpa - N84°E 33.46'  
 Set nail and remon. tag in NE. side Power pole - N28°W 54.88'  
 Set nail and remon. tag in E. side 7" Pine - S16°W 167.75'  
 Set nail and remon. tag in S. side Power pole - N89°E 60.03'



Signed by *Maurice J. Rosema* Date Dec. 10, 1994  
 Surveyor's Michigan License No. 27459

VanKooten - 1972 per L.C.R.C. rec. in L. 1, P. 769  
Iron  
Conc. fence post - NNW. 23.6'  
14" Catalpa - ENE. 63.18'  
Tele. pole - SSW. 84.6'

SURVEY &  
REMONUMENTATION

DEC 05 2000

Bonnema - 1981 per L.C.R.C. rec. in L. 4, P. 214  
1" iron

SECTION

Nail in NW. side 16" Catalpa - ENE. 33.41'  
Bolt spike in S. side Power pole - E. 59.97'  
P.K. nail in top of cedar post for underground M.B.T. - W. 27.36'  
P.K. nail in NE. side Power pole - NW. 54.85'

Joiner - 1981 per L.C.R.C. rec. in L. 4, P. 288  
C.I. mon.

Wood post near tele. ped. - W. 27.35'  
15" Catalpa - E. 33.44'  
Power pole - NW. 54.85'  
Fence post - E. 33.86'

Rosema - 1985 per L.C.R.C. rec. in L. 5, P. 201  
C.I. mon.

Nail in NW. side 16" Catalpa - ENE. 33.43'  
Bt. spike in S. side Power pole - E. 60.00'  
P.K. nail in top of cedar post for underground tele. - W. 27.34'  
P.K. nail in NE. side Power pole - NW. 54.88'