

RECORDED

93 DEC 15 AM 9:27

COMMISSION

Ottawa County remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Enjelle Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	K-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice J. Rosema, in a field survey on Aug. 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 Clapp - 1972 per L.C.R.C. recorded in Liber 1, Page 797. C.I.M. Blendon cor. (iron pipe) - E. 16.15' 48" Maple - NE. 63.98' 28" Maple - ENE. 99.14' c/l st. sign - SE. 52.58' T. pole - SE. 75.61' P. pole - SW. 88.51'	Joiner - 1982 per L.C.R.C. recorded in Liber 4, Page 348 C.I.M. T. pole - NE. 35.05' c/l st. sign - NE. 31.11' P. pole - SW. 64.38' c/l tele. ped. - NW. 25.20'
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

K-13 Found C.I. monument in monument box
Blendon corner (C.I. monument in monument box) - S90°E 16.15'
c/l base of street sign - S51°E 52.86'
Found nail and tag in SE. side T. pole - S28°W 43.77'
Found P.K. nail in NE. side P. pole - S41°E 78.02'
Found P.K. nail in SE. side P. pole - S49°W 86.17'

I hereby accept this corner as a correct and accurate perpetuation of the position of the original section corner.

Rosema - 1984 per L.C.R.C.
recorded in Liber 5, Page 152
C.I.M.
P.K. nail in SE. side P. pole - SW. 86.15'
Nail in SW. side 36" Maple - ENE. 64.03'
P.K. nail in E. side P. pole SE. 78.27'
Nail in NE. side T. pole - SSW. 43.45'
3/4" iron (K-1, T6N, R14W) - E. 16.30'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Set O.C. remon. cap in conc. above C.I. monument in monument box
Center of top of hydrant - N52°E 45.75'
Set nail and O.C. remon. tag in SE. side T. pole - S28°W 43.77'
Set nail and O.C. remon. tag in NE. side P. pole - S41°E 78.02'
Set nail and O.C. remon. tag in SE. side P. pole - S49°W 86.17'
On centerline of E-W bit. conc. road, centerline of N-S bit. conc. road - E. 10'±



Signed by Maurice J. Rosema
Surveyor's Michigan License No. 27459

Date Sept. 3, 1993