

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey T7N R14W L-1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

_____ Common corner
w/ L-13
Polkton Twp.

RECORDED

95 NOV 29 PM 1:36

Elizabeth Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steven Lampen, in a field survey on November 15 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1
Survey in L 8-P 192
Found "T" iron
2nd wood fence post W 30.62'
6"x8" fence post N 9.82'
6"x8" fence post E 19.48'
On fence lines E, W & N

No LCRC recorded
Old records of JK & A
Found "T" iron by Clapp in 1975 at intersection of fences
30" Ash NNE 111.33'
NE cor. R.R. tie fence post is W 0.10'

LCRC L 4-P 48
April 14, 1980
Found "T" iron NNE 111.33'
30" Ash stump W 30.60'
6"x8" fence post N 9.82'
6"x8" fence post E 9.48'

LCRC L 4-P 290
Jan. 5, 1982
Found "T" iron
Set cast iron mon.
Fence post W 30.60'
Fence post N 9.82'
Fence post E 9.48'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1
Found "T" iron at intersection of fence lines
NE cor. of R.R. tie fence post 0.05' W and 0.2' S
Nail & cap R.L.S. #23520 in E face R.R. tie fence post AZ 0° 00' 9.84'
Nail & cap R.L.S. #23520 in N face R.R. tie fence post AZ 90° 9.53'

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Robert D. Newell
RDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1
Ottawa County Remonumentation iron and cap
O.C. Remon. tag & nail E face R.R. tie fence post AZ 0° 9.64'
O.C. Remon. tag & nail N face R.R. tie fence post AZ 90° 9.33'
O.C. Remon. tag & nail S face 8" Elm AZ 267° 8.00'
O.C. Remon. tag & nail E face 6" Hawthorn AZ 20° 14.13'
N-S fence to North
On line with E-W fence line



Signed by Steven Lampen Date November 17, 1995
Surveyor's Michigan License No. 37279