

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 18 PM 4: 54

Phyllis Callman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

Ottawa <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	L-9 (S $\frac{1}{4}$ cor. Sec. 24)
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Maurice J. Rosema, in a field survey on Dec. 6, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-9	GLO 1832 by Britain	LCRC rec. in L 1, P 217	LCRC rec. in L 2, P 185
	Post	(1972)	(1973)
	20" Beech - N36°W	1" sq. iron	1" sq. iron
	19 lks	CP pole - N40°W 49.95'	Nail in P pole - SE 58.53'
	30" Beech - S19°W	CP pole - S40°W 55.80'	Nail in P pole - SW 56.47'
	17 lks	CP pole - S40°E 58.02'	Nail in P pole - NE 56.30'
		CP pole - N30°E 55.74'	Nail in T pole - NW 46.50'

Information from the files of Tru-Line Surveying P.C. (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9
 Replaced $\frac{1}{2}$ " rerod in mon. box with 5/8" x 3' steel rod with remon. cap in mon. box
 Center of top of hydrant - NW 52.90'
 Found nail in W side 15" Maple - NNE 52.11'
 Found PK nail in E side P pole - SE 58.53'
 Found PK nail in NW side P pole - SW 56.75'

P.A. 345 OTTAWA COUNTY


PEER APPROVED: 12-9-96

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

M. J. Rosema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9
 5/8" x 3' steel rod with remon. cap in mon. box
 Center of top of hydrant - N36°W 59.90'
 Nail and remon. tag in W side 15" Maple - N28°E 52.11'
 Nail and remon. tag in E side 24" Maple - N53°E 71.12'
 Nail and remon. tag in E side P pole - S28°E 58.53'
 Nail and remon. tag in NW side P pole - S39°W 56.75'
 At centerline "X" of road E-W-S



Signed by *M. J. Rosema* Date Dec. 9, 1996
 Surveyor's Michigan License No. 27459