

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 18 PM 4: 54

For corners in

Ottawa <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>14W</u>	M-6 (E $\frac{1}{4}$ cor. Sec. 13)
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

*D. J. ...*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Maurice J. Rosema, in a field survey on Sept. 2, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 M-6

Original gov't cor. set in 1837 by John Mullett	MVK Associates (info. per company files) T-iron
Set post 10" Beech S53°W 20 lks.	Tru-Line surveying P.C. (per company files) T-iron
9" Hemlock N19°W 9 lks.	On E edge of gravel drive to N c/l E-W gravel road S 20'±

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 M-6

Found T-iron, replaced with 3/4" X 2' steel bar with O.C. remon. cap  
 On E edge of gravel drive to N  
 c/l E-W gravel road S 20'±

P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 12-9-96

*M. J. Rosema*

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-6

3/4" X 2' steel bar with O.C. remon. cap	
Set nail and O.C. tag in NW side P pole	S60°W 100.60'
Set nail and O.C. tag in E side 13" Maple	S21°E 97.08'
Center of base of stop sign	S69°W 28.92'
Set nail and O.C. tag in W side fence post	N12°E 75.79'
Set nail and O.C. tag in W side mailbox post	S52°E 18.20'
Set nail and O.C. tag in S side fence post	N51°E 18.11'
Set nail and O.C. tag in top of T. box post	S29°W 59.88'
On E edge of gravel drive to N c/l E-W gravel road	S 20'±



Signed by *M. J. Rosema* Date Nov. 14, 1995  
 Surveyor's Michigan License No. 27459