

**SURVEY &  
REMONUMENTATION**

Ottawa County Remonumentation

APR 05 1996

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**COMMISSION**

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>T7N</u> R <u>R14W</u>	M-10
	T _____ R _____	(E <sup>1</sup> cor of
	T _____ R _____	Section 25)
	T _____ R _____	Allendale Twp
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECORDED**

95 NOV 29 PM 1:47

*Phyllis Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Maurice J. Rosema, in a field survey on Sept. 21, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-10  
Glo - 1837 (John Mullett (D.S.) 9" Sugar S8°W 26 lks L.C.R.C. recorded in Liber 6 Page 164 - Sept. 3, 1991 (over)  
L.C.R.C. recorded in Liber 5 Page 243 - Aug. 1, 1986 (over)  
L.C.R.C. recorded in Liber 2 Page 621 - July 3, 1974 (over)

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11-20-95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10  
Found C.I. Monument in monument box  
Street sign SW 92.84'  
Found nail in 13" Elm SE 97.12'  
Found x in Conc. Culv. W 33.30'

*M. J. Rosema*  
2077



I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Found C.I. Monument in monument box  
Set nail and Ottawa County remon. tag in SE side P pole S66°W 46.32'  
Set nail and Ottawa County remon. tag in N side wood post N86°E 45.70'  
c/l street sign (E post) S20°W 92.84'  
Set nail and Ottawa County remon. tag in SW side 13" Elm S55°E 97.12'  
c/l top tele ped N58°W 56.42'  
Found X cut on concrete culvert N90°W 33.30'  
On c/l N-S bit. conc. road

Signed by *M. J. Rosema* Date October 21, 1995  
Surveyor's Michigan License No. 27459

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, REVISED MAY 14, REVISED JAN.

M-10 T7N, R14W

L.C.R.C. recorded in Liber 2, Page 621  
- September 27, 1974

Copperweld Rod in Monument box  
8" Box Elder S60°E 97.08'  
Face of 24" Stump N60°W 76.0'

L.C.R.C. recorded in Liber 5, 243  
- August 6, 1986

1/2" Copper rod in Monument Box  
Nail in fc 24" Stump WNW 76.17'  
Centerline E'ly steel sign post SSW 92.74'  
Nail and tag in S side 12" Elm SE 97.20'  
"T" on S end 20" Conc. Culv. W 33.31'  
Tree row to E - S 48'  
On Tree row to W  
On centerline N-S B.T. road

L.C.R.C. recorded in Liber 6, 1991  
- October 11, 1991

C.I. Monument  
6" Ash SE 68.90'  
Centerline hyd. SW 107.18'  
10" Poplar NW 84.87'  
Iron in shoulder NE 50.92'

\$ 11.00 CORNER