

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 DEC -2 PM 1:13

SECTION

For corners in
OTTAWA
(County)

Located In: ROBINSON
(Township)

Corner Code #A-3

Ray [Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MICH.

- 1. Public Land Survey T 7N R 15W S.W. Cor. Sec. 6
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____ COMMON CORNER
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

PL 345 OF OTTAWA COUNTY

APPROVED 11/15/99

I, Robert E. Lemke, surveyor, in a field survey on September 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3
FOUND CAST IRON MONUMENT IN MONUMENT BOX 9" BELOW THE TOP OF THE MONUMENT BOX.

FOUND NAIL ON EAST SIDE OF 32" OAK 6" ABOVE GROUND. N.W. 39.90'
FOUND NAIL ON N.E. SIDE OF ABOVE 32" OAK 12" ABOVE GROUND. N.W. 41.11'
MEASURED TO SIGNAL ON N.W. 'LY SIDE OF 20" OAK 12" ABOVE GROUND (DID NOT FIND WITNESS) S.E. 69.5'
DID NOT FIND ANY OTHER WITNESSES



THIS CORNER(A-3) WAS DETERMINED TO BE COMMON WITH M-3, SECOR. SECTION 1, GRAND HAVEN TOWNSHIP IN REMON LIBER 2, PAGE 69 BY TOM JOINER IN DECEMBER OF 1994. M-3 WAS PEER APPROVED ON DECEMBER 12, 1994. ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 CAST IRON MONUMENT IN MONUMENT BOX 9" BELOW THE TOP OF THE MONUMENT BOX.

Fd. NAIL WITH OTTAWA COUNTY REMON. TAG ON N.E.'LY SIDE OF 32" OAK 1' ABOVE GROUND N.45°W. 41.11'
SET NAIL WITH OTTAWA COUNTY REMON. TAG ON S'LY SIDE OF 36" OAK 1.5' ABOVE GROUND N.75°E. 123.11'
Fd. NAIL WITH OTTAWA COUNTY REMON. TAG ON W'LY SIDE OF 20" OAK 0.6' ABOVE GROUND S.30°E. 70.36'
SET NAIL WITH OTTAWA COUNTY REMON. TAG ON E'LY SIDE OF 13" OAK 0.2' ABOVE GROUND S.45°W. 90.96'
CENTERLINE OF 144TH AVENUE 0.5' WEST AND CORNER IS ON CENTERLINE OF JOHNSON STREET.
M3 TO B3(T7N, R15W) IS 2739.11' PER SDI MEASURE
M2-A3(T7N, R15W) PER SDI MEASURE IS 2647.42'.

OCCUPATION LINE (CONSISTING OF TREE LINE AND CHAIN LINK FENCE) IS 1324'+/- NORTH OF A-3

Signed by *Robert E. Lemke*

Date 11-15-1999

For SDI CONSULTANTS, LTD

Surveyor's Michigan License No. 40160

\$11.00 CORNER
Receipt #64945

SEE BACK

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
JAN. 28, 1971 REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

FEB 24 2000

SECTION

OTTAWA COUNTY
ROBINSON TOWNSHIP
TOWN 7 NORTH, RANGE 15 WEST

A-3

A. Description of original monument and accessories and/or subsequent restoration

-G.L.O.

WEST BETWEEN SEC'S 6 & 7
81.45 WEST BOUNDARY AT POST & SET COR
TO SEC'S 6 & 7
MAY 20, 1832 (CALVIN BRITAIN)

20" PINE S. 59° W. 25 LINKS
20" PINE N. 65° W 6 LINKS

-OTTAWA COUNTY ROAD COMMISSION NOTES

SET ½" GAS PIPE 12-10-57 (NO INITIALS)
14" B. OAK N.W. 40.3'
12" W. OAK N.E. 49.2'
12" B. OAK N. 20° E. 60.8'
12" R. OAK S.W. 118.4'
N. 56° W. 39.4' IRON
N. 43° 30' E. 48' IRON

-THOMAS JOINER, L.C.R.C. RECORDED LIBER 3 PAGE 380, RECORDED JULY 27, 1979

FD. 1" IRON

SET CAST IRON MONUMENT

30" OAK	NW	39.90'
48" OAK	NE	59.70'
18" OAK	SE	69.60'
TELE. POLE	SE	46.50'

JOINER SHOWS SAME WITNESSES ON RECORDED BOUNDARY SURVEY:

LIBER 8 PAGE 888 RECORDED: 10-11-88

LIBER 8 PAGE 889 RECORDED: 10-11-88

-JOHN CLAPP, HOLLAND ENGINEERING, RECORDED BOUNDARY SURVEY, LIBER 8 PAGE 615, 5-19-95

1" IRON

30" OAK	NW	39.90'
48" OAK	NE	59.70'
18" OAK	SE	69.60'
TP	SE	46.50'
ST. SIGN	NW	24.65'

A-4 NORTH TO A-3 = N00°10'30"W 2650.24

-GERALD FORD, HOLLAND ENGINEERING, RECORDED BOUNDARY SURVEY, LIBER 8 PAGE 907, 3-20-97

(FORD SHOWS SAME WITNESSES ON RECORDED BOUNDARY SURVEY, LIBER 9 PAGE 43, 12-8-97)

CAST IRON MONUMENT

30" OAK	NW	39.90'
48" OAK	NE	59.70'
18" OAK	SE	69.60'
TP	SE	46.50'

A-3 EAST TO B-3 = N89°44'00"E 2739.12

-FIELD NOTES FOR JOINER BOUNDARY SURVEY

A-3 NORTH TO A-2 = N02°19'35"E 2647.76'