

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 DEC -2 PM 1:12

SECTION

For corners in

OTTAWA Located In: ROBINSON  
(County) (Township)

Corner Code # B-7

- 1. Public Land Survey T 7N R15W N 1/4 OF SEC. 19  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

*Harry [Signature]*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert E. Lemke, surveyor, in a field survey on SEP. 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

545 OTTAWA COUNTY

APPROVED 9/13/99  
YDZ

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 5/8" IRON ROD WITH CAP #18987 IN CENTERLINE OF 12' TWO-TRACK ROAD(BUCHANAN) 1.8' BELOW GRADE.  
Found all witnesses from the L.C.R.C. SHOWN ON THE BACK.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-7 SET 36" BY .75" STANDARD REMON MARKER WITH CAP
- SET NAIL AND OTTAWA COUNTY REMON. TAG IN N.W. SIDE OF 9" BASSWOOD N 30°E 27.81'(2.4') ABOVE GRADE
- SET NAIL AND OTTAWA COUNTY REMON. TAG IN EAST SIDE OF 24" BASSWOOD N 30°W 37.83'(4') ABOVE GRADE
- SET NAIL AND OTTAWA COUNTY REMON. TAG IN N.W. SIDE OF 22" TWIN ASH S 45°W 20.63'(1.4') ABOVE GRADE
- SET NAIL AND OTTAWA COUNTY REMON. TAG IN NORTH SIDE OF 16" MAPLE S 45°E 26.13'( 2') ABOVE GRADE
- FOUND 1/2" IRON (CAP#18987) SOUTH 33.03

Signed by Robert E. Lemke

Date 9-20-1999

For SDI CONSULTANTS, LTD

Surveyor's Michigan License No. 40160



SEE BACK

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS  
JAN. 28, 1971 REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

\$11.00 CORNER  
Receipt #64945

OTTAWA COUNTY  
ROBINSON TOWNSHIP  
TOWN 7 NORTH, RANGE 15 WEST

B-7

A. Description of original monument and accessories and/or subsequent restoration

-G.L.O.

40.0 SET 1/2 MILE POST  
HEMK 12 N65W 36  
DO 10 N64E 9

WITNESS CARD FROM T. & H. ASSOCIATES  
STAKE

- A. SYC 30 N 55 W 24
- B. ASH 10 W 3
- C. MAPLE 10 N 30 W 24

-CARL ENGLERT JR., L.C.R.C. RECORDED LIBER 2 PAGE 411, DATED: 11-29-73  
SET 5/8" ROD ON TRUE LINE BETWEEN SECTION CORNERS  
BY SINGLE PROPORTIONATE MEASUREMENT

- 1. 14.50' 6" BASSWOOD
- 2. 20.62' 14" ASH
- 3. 26.23' TREE
- 4. 20.11' 6" BASSWOOD

FEB 24 2000

SECTION