

RECORDED

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 DEC -2 PM 1: 13

Ray S. [Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MI

SECTION

For corners in

OTTAWA
(County)

Located In: ROBINSON
(Township)

Corner Code # C-4

- 1. Public Land Survey T 7N R 15W
 T _____ R _____ WEST 1/4 CORNER

 T _____ R _____ SECTION 8
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7						8			9			10
5													
6		18					17			16			15
7													
8													
9													
10													
11													
12													
13													

I, Robert E. Lemke, surveyor, in a field survey on September 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
SEE BACK OF SHEET FOR CORNER HISTORY

REMOVED 9/13/99
YDN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-4
FOUND CAST IRON MONUMENT 13" BELOW ROAD GRADE

- FOUND NAIL IN NW SIDE 13" CHERRY 8" ABOVE GROUND NW 54.84'
- FOUND NAIL WITH TAG (CAN'T READ) NE SIDE OF 14" OAK 12" ABOVE GROUND SE 67.19'
- FOUND NAIL WITH TAG (CAN'T READ) SE SIDE OF 30" OAK 4" ABOVE GROUND SW 38.41'

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-4
CAST IRON MONUMENT 13" BELOW ROAD GRADE

- SET NAIL WITH OTTAWA COUNTY REMON TAG NW SIDE OF 13" CHERRY 9" ABOVE GROUND N45°W 54.84'
- SET NAIL WITH OTTAWA COUNTY REMON TAG SOUTH SIDE OF 19" PINE 12" ABOVE GROUND N40°E 80.17'
- SET NAIL WITH OTTAWA COUNTY REMON TAG NE SIDE 14" OAK 13" ABOVE GROUND S25°E 67.19'
- SET NAIL WITH OTTAWA COUNTY REMON TAG SE SIDE 30" OAK 5" ABOVE GROUND S35°W 38.41'

CENTER LINE OF 136TH AVENUE 2 FEET WEST
CENTER LINE OF FERRIS STREET 3 FEET NORTH

Signed by *Robert E. Lemke*
For SDI CONSULTANTS, LTD

Date 9-20-1999

Surveyor's Michigan License No. 40160



SEE BACK

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
JAN. 28, 1971 REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1995

\$11.00 CORNER
Receipt #64945

FEB 24 2000

SECTION

OTTAWA COUNTY
ROBINSON TOWNSHIP
TOWN 7 NORTH, RANGE 15 WEST

C-4

A. Description of original monument and accessories and/or subsequent restoration

-G.L.O.

40.0 SET 1/2 MILE POST
MAY 1832 (CALVIN BRITAIN)

10" PINE	N40W	17 LINKS
8" PINE	S71E	9 LINKS

-OTTAWA COUNTY ROAD COMMISSION NOTES

FOUND STAKE SET IRON ROD

BEECH N 6 LINKS
16" R. OAK SW 38.0'
4" R. OAK NW 36.5'

FOUND IRON (1967 JPC)

TP NE 83.54'
20" OAK SW 57.12'
6" OAK SE 66.74'
18" OAK NW 60.41'
ST. SIGN SE 37.10'

-CARL P. ENGLERT JR., L.C.R.C. LIBER 2 PAGE 107 RECORDED: 4-13-1973
1" PIPE

SW	38.45	30" OAK
NW	54.88	12" CHERRY
NE	84.03	T.P.
SE	67.20	10" OAK

-KIRK L. VAN ORDER, L.C.R.C. LIBER 4 PAGE 60 RECORDED: 5-15-1980

FOUND TWO 1" PIPES BESIDE EACH OTHER

SET CAST IRON MONUMENT INSCRIBED "SECTION CORNER"

30" BLACK OAK	S.W.	38.45'
12" BLACK CHERRY	N.W.	54.88'
TEL. POLE	N.E.	84.03'
10" WHITE OAK	S.E.	67.20'
ANGLE IRON	WEST	33.0'

-MAURICE ROSEMA, L.C.R.C. LIBER 5 PAGE 270 RECORDED: 3-18-1987

FOUND CAST IRON MONUMENT

NAIL AND TAG IN NE SIDE 12" OAK	SE	67.20'
NAIL AND TAG IN NE SIDE 18" OAK	NW	75.02'
NAIL IN SE SIDE 30" OAK	SW	38.40'
NAIL IN SE SIDE T POLE #331	ENE	84.18'
TOP OF "T" FENCE POST	W	32.80'