

**SURVEY &
REMONUMENTATION**

APR 25 1995

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:35

COMMISSION

For corners in

Ottawa
(County)

Located In:
Robinson Twp.

Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|---------------------|
| 1. Public Land Survey | T | <u>7N</u> | R | <u>15W</u> | <u>C-6</u> |
| | T | | R | | <u>W 1/4 Corner</u> |
| | T | | R | | <u>Section 17</u> |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Phyllis Kellman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Carl P. Englert, in a field survey on April 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

1. Description of original monument and accessories and/or subsequent restoration:
C-6 1/4 corner common to Sections 17 & 18
Original gov't corner set May, 1832
by Calvin Britain D.S.

Set Post

Maple 12" S62°E 20 Links
Do 16" N62°W 5 Links

L.C.R.C. Liber 3, Page 194
Found Iron Pipe, Set Cast Iron Monument Inscribed "Ottawa County Section Corner"
14" Red Pine NE 40.17
16" Red Pine ESE 32.30
22" Maple W 46.99
Power Pole WNW 47.44
30" Maple NW 56.78

(See Back of Page)

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-6 1/4 corner common to Sections 17 & 18
Found 4" Harrison Cast Iron Mon. 10" deep 9' +/- East of Road Centerline
Found 22" Maple W. 46.99' +/- (No Nail)
Found P.P. W.N.W. 47.44' +/- (No Nail)
Found 30" Maple N.W. 56.78' +/- (No Nail)

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

Phyllis Kellman

Accepted as a careful and faithful perpetuation of the original position of the corner.

4. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 1/4 corner common to Sections 17 & 18
4" Harrison Cast Iron Mon.
O.C. Remon. Tag & Nail in S.E. Side 24" Aspen S12°E 103.72'
O.C. Remon. Tag & Nail in N Side 15" Scotch Pine S79°E 51.44'
O.C. Remon. Tag & Nail in N.E. Side 36" Maple N52°W 57.19'
O.C. Remon. Tag & Nail in S. Side 30" Maple N89°W 47.92'
Cut "X" in Conc. Culvert S65°W 31.10'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 11/21/94



Liber 1, Page 297

C-6 Found Angle Iron

Nail in Face of 18" Oak	SE	27.06'
Nail in Face of 12" Pine	NE	29.59'
Nail in Face of 18" Maple	W	47.11'
Nail in Face of 12" Pine	E	31.90'
Nail in Face of 12" Pine	NE	39.84'

CODE # 120 A
2000000 9.00
CODE # 150 A
10000 2.00