

SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:35

COMMISSION

or corners in

Ottawa
(County)

Located In:
 Robinson Twp.

Corner Code ##

Public Land Survey	T <u>7N</u> R <u>15W</u>	C-7
	T _____ R _____	S.W. Corner
	T _____ R _____	Section 17
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Richard Robinson
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Carl P. Englert, in a field survey on April 20, 19 94,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

C-7 corner common to Sections 17, 18, 19 & 20
 Original gov't corner set May, 1832
 by Calvin Britain D.S.

Liber 3, Page 194

Found Angle Iron Over Iron Pipe,
 Replaced with Cast Iron Monument
 Inscribed "Ottawa County Section
 Corner."

Set Corner

W. Oak 10" N48°E 25 Links
 Do 6" S39°W 23 Links

7" Jack Pine NE 67.92'
 4" Ash SE 51.60'
 18" Oak SW 62.65'
 Power Pole NW 55.35'

(See Back of Page)

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 corner common to Sections 17, 18, 19 & 20
 Found 4" Harrison Cast Iron Mon. 4" Deep
 Found P.P. N.W. 55.29'
 Found T.P. N.W. 52.34'
 Found 18" Oak S.W. 62.65'
 Found 7" Jack Pine 67.92'+/- (No Nail)

Accepted as a careful and faithful perpetuation of the position of the original corner.


P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

Barney D. Medewald

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 corner common to Sections 17, 18, 19 & 20
 4" Harrison Cast Iron Mon.
 O.C. Remon. Tag & Nail in W. Side 16" Spruce N13°E 98.04'
 O.C. Remon. Tag & Nail in S.W. Side P.P. N54°W 56.21'
 O.C. Remon. Tag & Nail in N.W. Side 20" Oak S43°W 63.15'
 O.C. Remon. Tag & Nail in S.E. Side 12" Ash S27°E 51.89'
 in Centerline Gravel Road N&S, Centerline Gravel Road
 East 6' +/- N. of corner



Signed by Carl P. Englert Jr.

Date 11/21/94

Surveyor's Michigan License No. 18987

Liber 1, Page 517

C-7 Found Iron Pipe - Set Angle Over

Nail in Face of Twin 18" Maple	SW	61.00'
Nail in Face of Power Pole	NW	55.29'
Nail in Face of Telephone Pole	NW	52.34'

Liber 1, Page 700

C-7 Iron Stake

S.E. 74.83 P.P.

S.W. 83.73 P.P.

W.N.W. 34.15 Sign Post

CODE #
CORNER
3000
3000

CODE #
CORNER
3000
3000