

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 DEC -2 PM 1:13

SECTION

*Gary Schell*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
OTTAWA  
(County)

Located In: ROBINSON  
(Township)

Corner Code #C-8

1. Public Land Survey	T	<u>7N</u>	R	<u>15W</u>	W1/4 of Sec. 20
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Lemke, surveyor, in a field survey on Sep. 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

STATE OF MICHIGAN COUNTY

APPROVED 9/13/99  
*YDM*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 4" DIAMETER CAST IRON MONUMENT IN MONUMENT BOX 12" BELOW GRADE AT THE INTERSECTION OF RICH STREET AND 136<sup>TH</sup> AVE.
- 8) FOUND 11" RED PINE NE AND MEASURED 63.4' S.W. FACE OF TREE
- 7) FD P. POLE NE AND MEASURED 48.2'
- 6) FD 29" OAK SE AND MEASURED 60.45'
- 5) FOUND NAIL IN 12" WHITE PINE SW AND MEASURED 60.80'

And is accepted as a careful and faithful perpetuation of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-8 CAST IRON MONUMENT IN MONUMENT BOX.
- SET NAIL AND OTTAWA COUNTY REMON. TAG IN S.W. FACE OF 11" PINE N 50°E 63.35' (1.4') ABOVE GRADE
- SET NAIL AND OTTAWA COUNTY REMON. TAG IN S.W. FACE OF POWER POLE N 70° E 48.27' (2') ABOVE GRADE
- SET NAIL AND OTTAWA COUNTY REMON. TAG IN NORTH SIDE OF 32" OAK S 45°E 60.61' (1') ABOVE GRADE
- SET NAIL AND OTTAWA COUNTY REMON. TAG IN N.E. FACE OF 12" WHITE PINE S 50°W 60.80' (4') ABOVE GRADE
- MONUMENT IS AT THE INTERSECTION OF RICH STREET AND 136<sup>TH</sup> AVE.

Signed by Robert E. Lemke  
For SDI CONSULTANTS, LTD

Date 9-20-1999

Surveyor's Michigan License No. 40160



\$11.00 CORNER  
Receipt #64945

SEE BACK

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS  
JAN. 28, 1971 REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

FEB 24 2000

SECTION

OTTAWA COUNTY  
ROBINSON TOWNSHIP  
TOWN 7 NORTH, RANGE 15 WEST

C-8

A. Description of original monument and accessories and/or subsequent restoration

-G.L.O.

40.00 SET 1/2 MILE POST  
BEECH 10 N63E 37  
DO 10 S63W 23

-JOHN CLAPP, RECORDED L.C.R.C. LIBER 1 PAGE 179 DATED: 11-30-1971  
FOUND IRON

1.	NAIL IN FACE OF 10" PINE	NE	45.35'
2.	NAIL IN FACE OF 24" OAK	SE	60.75'
3.	NAIL IN FACE OF TEL. POLE	SW	44.27'
4.	NAIL IN FACE OF ST. SIGN	SE	43.70'

-THOMAS JOINER, RECORDED L.C.R.C. LIBER 3 PAGE 231 DATED: 11-14-1977  
IRON, FOUND 1/2" PIPE USING OLD TIES RECORDED (AS SHOWN ABOVE)

SET CAST IRON MONUMENT INSCRIBED  
"OTTAWA COUNTY SECTION CORNER."

5.	SET NAIL & TIE TAG IN 8" WHITE PINE	SW	60.91
6.	SET NAIL & TIE TAG IN 29" OAK	SE	60.63
7.	SET NAIL & TIE TAG IN P. POLE	NE	48.12
8.	SET NAIL & TIE TAG IN 6" RED PINE	NE	63.40