

# SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12: 35

For corners in **COMMISSION**

*Reginald Williams*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In: Robinson Twp.	Corner Code # C-10
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>W 1/4 Corner</u>
	T _____ R _____	<u>Section 29</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Carl P. Englert, in a field survey on March 17, 19 94,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:  
C-10 1/4 corner common to Sections 29 & 30  
Original gov't corner set May 1832  
by Calvin Britain D.S.

L.C.R.C. Liber 4, Page 282  
(1/5/82)  
Found Iron Bar, Set C.I.M.  
N.W. 37.60' P.P.  
N.E. 39.18' Guy Pole  
S.E. 39.55' St. Sign

Set Post  
Tamarack 6" S87°E 12 Links  
Do 5" N60°W 9 Links

(See Back of Page)

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
C-10 1/4 corner common to Sections 29 & 30


Found 4" Harrison Cast Iron Mon. with Broken Top  
Found N.W. 37.60' P.P.  
Found N.E. 39.18' Guy Pole

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/21/94  
*Wendy D. Medowald*

Accepted as a careful and faithful perpetuation of the  
original position of the corner.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-10 1/4 corner common to Sections 29 & 30.

4" Harrison Cast Iron Monument with Broken Top  
O.C. Remon. Tag & Nail in W. Side P.P. S50°W 327.12'  
O.C. Remon. Tag & Nail in N. Side P.P. N84°W 352.58'  
O.C. Remon. Tag & Nail in N.E. Side P.P. N43°W 37.67'  
O.C. Remon. Tag & Nail in S.E. Side Guy P. N49°E 39.26'  
Monument in center of Intersection 6" deep



Signed by Carl P. Englert  
Surveyor's Michigan License No. 18987

Date 11/21/94

A. Description of original monument and accessories and/or subsequent restoration.

C-10 L.C.R.C. Liber 2, Page 413 (11/30/73)

Found 5/8" Rod

N.W. 37.60' P.P.

N.E. 39.18' Guy Pole

S.E. 39.55' St. Sign

1957  
# 202  
# 202  
# 202