

# SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:36

*Daphne Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

or corners in

<u>Ottawa</u> (County)	Located In: Robinson Twp.	Corner Code # C-11
Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>SW corner</u>
	T ___ R ___	<u>Section 29</u>
	T ___ R ___	_____
	T ___ R ___	_____
Property Controlling in Section	S ___ T ___ R ___	_____
Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11		▲	✕										
12	31	32	33	34	35	36							
13													

Carl P. Englert in a field survey on March 18, 1994,  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:  
C-11 corner common to Sections 29,30,31 and 32.  
Original gov't corner set a May 1832 by Calvin Britain D.S.  
Set Corner  
Tamarak 10" S59°E 1.14 chains  
Do 4" S64°W 11 Links  
LCRC Liber 2, Page 35  
Set CIM from ties  
Angle Iron East 33'  
10" Pine W.N.W. 75.03'  
P.P. S.S.W. 77.65'  
10" Poplar N.N.E. 94.40'  
Fence Cor. Post E. 33.46'


Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
C-11 corner common to Sections 29,30,31 and 32.  
Found 4" Harrison Cast Iron Mon. with Broken Top 15" deep.  
Found 10" Pine N.W. 75.03  
Found P.P. S.S.W. 77.65'  
Found Fence corner Post East 33.5' +/-

Accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/21/94

*Arday D. Hedewald*

Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-11 corner common to Sections 29,30,31 and 32.  
4" Harrison C.I.M. with broken top  
O.C. Remon. Tag & Nail in W. side P.P. N05°W 271.88'  
O.C. Remon. Tag & Nail in S. side 14" Scotch Pine N82°W 74.90'  
O.C. Remon. Tag & Nail in W. side P.P. S19°W 78.01'  
O.C. Remon. Tag & Nail in W. side P.P. S04°W 419.42'  
6' +/- West of the centerline of dirt road.



Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

Date 11/17/94