

**SURVEY &  
REMONUMENTATION**

APR 25 1995

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
94 DEC -8 PM 12:36

*Phyllis Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in **COMMISSION**

Ottawa (County) Located In: Robinson Twp Corner Code #     

1. Public Land Survey T 7N R 15W C-12  
T      R      W. 1/4 corner  
T      R      Section 32  
T      R     

2. Property Controlling S      T      R       
in Section S      T      R     

3. Miscellaneous S      T      R       
Property in Sec. S      T      R     

4. Lot No.     , Recorded Plat     

5. Private Claims     

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Carl P. Englert, in a field survey on March 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
C-12 1/4 corner common to Sections 31 and 32.  
Original gov't corner set May, 1832  
by Calvin Britain D.S.  
Set Post  
Tamarak 7" N18°W 85 links  
Do 10" S41°E 2.02 Chains

Set CIM in Place of R.R. Rail  
10" Pine N.E. 57.95'  
P.P. S.W. 30.57'  
Center Line Culvert N. 11.45'  
W. end culvert N.W. 21.8'  
E. end culvert N.E. 18.5'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
C-12 1/4 corner common to Sections 31 and 32.  
Found 4" Harrison Cast Iron Mon. 4' West of Centerline dirt road  
3" deep.  
Found P.P. S.W. 30.57  
Found Center Line Culvert North 11.5'

Accepted as a careful and faithful perpetuation of the Position of the original corner.

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/21/94  
*Robert P. [Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-12 1/4 corner common to Sections 31 and 32.  
4" Harrison Cast Iron Mon.  
O.C. Remon. Tag & Nail in N.W. side 6" Poplar N49°E 91.60'  
O.C. Remon. Tag & Nail in N. side P.P. S86°W 20.16'  
O.C. Remon. Tag & Nail in the N.W. side P.P. S40°W 31.04'  
O.C. Remon. Tag & Nail in the E. side P.P. N04°W 291.62'  
"x" in West end C.M.P.



Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

Date 11/17/94