

**SURVEY &
REMONUMENTATION**

APR 25 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:35

Edythe A. Hillman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In: Robinson Twp.	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>D-7</u>
	T _____ R _____	<u>S 1/4 Corner</u>
	T _____ R _____	<u>Section 17</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert, in a field survey on April 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-7 1/4 Corner Common to Sections 17 & 20
Original gov't corner Set May, 1832
by Calvin Britain D.S.

L.C.R.C. Liber 3, Page 231
Set Cast Iron Monument Inscribed
"Ottawa County Section Corner"

Set Post
Beech 15" S52°E 34 Links
Do 12" N63°W 30 Links

P. Pole NE 100.32 Set Tie Tag
P. Pole S 41.31 Set Tie Tag
6" Scotch Pine NW 50.41 Set Tie Tag
6" Scotch Pine NNW 35.03 Set Tie Tag

(See Back of Page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7 1/4 corner common to Sections 17 & 20

Found 4" Harrison Cast Iron Mon. in Centerline Gravel Road 4" deep
Found Iron Stake 33'N & 33'S
Found P.P. NE 100.32'

PA. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

Arday D. McDowell

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7 1/4 corner common to Sections 17 & 20
4" Harrison Cast Iron Mon. 4" Deep
O.C. Remon. Tag & Nail in W. Side P.P. S4°W 41.68'
O.C. Remon. Tag & Nail in N.W. Side P.P. N70°E 100.61'
O.C. Remon. Tag & Nail in W. side 8" Sassafras N6°W 45.59'
O.C. Remon. Tag & Nail in S. Side 12" Pine N68°W 78.48'



Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 11/21/94

D-7 Found 2" Iron Pipe	
Set Steel Bar in Pipe	
Nail in Face of 6" Sassafrass	NNW 34.95'
Nail in Face of 6" Sassafrass	NE 30.87'
Nail In Face of 4" Pine	SW 36.03'
Found Steel Bar	

130 #
1.00
0.17
2.00
130 #
1.00
0.17
2.00