

**SURVEY &
REMONUMENTATION**

APR 25 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:35

Polina A. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In: <u>Robinson Twp</u>	Corner Code #/
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>D-13</u>
	T _____ R _____	<u>S 1/4 Corner</u>
	T _____ R _____	<u>Section 32</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Carl P. Englert, in a field survey on March 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

4. Description of original monument and accessories and/or subsequent restoration:

D-13 South 1/4 corner Section 32
Original gov't corner set May, 1832
by Calvin Britain D.S.

Tamarack 10" is Post

LCRC Liber 6, Page 145
Raised CIM
Nail in P.P. S.E. 66.17'
16" Oak N.N.E. 44.28'
24" Maple W.S.W. 91.60'
Olive corner West 131.53'

(See Back of Page)

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 South 1/4 corner Section 32

Found 3" Harrison Cast Iron Mon. in Mon. Box.
Found P.P. S.E. 66.17'
Found 16" Oak N.N.E. 44.28'
Found 24" Maple W.S.W. 91.60'
Olive corner West 131.53'

Accepted as a careful and faithful perpetuation of the original position of the corner.

OTAWA COUNTY
FEER APPROVED 11/21/94
Polina A. Williams

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 South 1/4 corner Section 32

3" Harrison C.I.M. in Mon. Box on pavement centerline
O.C. Remon. Tag & Nail in N.E. side P.P. S58°E 66.13'
O.C. Remon. Tag & Nail in N.W. side 28" Maple S72°W 91.51'
O.C. Remon. Tag & Nail in E. side 8" Oak N19°W 119.46'
O.C. Remon. Tag & Nail S.E. side 20" Oak N16°E 44.22'
Olive corner W. 131.53'



Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 11/17/94

A. Description of original monument and accessories and/or subsequent restoration:

D-13 LCRC Liber 2, Page 37
Set C.I.M. in Place of Iron Pipe
9" Oak N.E. 53.62'
Centerline Street Sign N.E. 26.30'
P.P. S.E. 65.70'
20" Maple S.W. 90.26'
T,P. N.W. 97.54'

2006 #
2007 #
2008 #
2009 #
2010 #
2011 #
2012 #
2013 #
2014 #
2015 #
2016 #
2017 #
2018 #
2019 #
2020 #
2021 #
2022 #
2023 #
2024 #
2025 #
2026 #
2027 #
2028 #
2029 #
2030 #