

SURVEY & REMONUMENTATION

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|------------------------------------|------------------------------|------------------------------|
| <u>OTTAWA</u> (County) | Located in: Robinson Twp. | Corner Code # E - 4 |
| 1. Public Land Survey | T 7 N R 15 W | West 1/4 corner Section 9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECORDED

95 NOV 29 PM 1:48

Richard R. Kallman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Carl P. Englert, Jr., in a field survey on October 16, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E - 4 1/4 corner common to Sections 8 & 9
 Original corner set May, 1832.
 By Calvin Britain, D.S.
 Set 1/2 mile post
 Hemlock 40" South 17 Links
 Beech 18" N 15° E 26 Links
 see other side

LCRC Liber 1, Page 405
 May 9, 1972
 Found Iron Pipe
 Nail in face of 12" Pine E. 39.88'
 Nail in face of 8" Pine NE 51.50'
 Nail in face of 6" Pine SE 59.53'
 Fence Corner SE 49.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E - 4 1/4 corner common to Sections 8 & 9
 Found 4" CIM in Mon. Box 1.4'± W. of CL asphalt Road
 Found 12" Pine E. 39.88'
 Found T.P. SW 54.20'
 Found P.P. SE 76.54'
 Found 10" Pine SE 59.30'

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 11-20-95

Maday D. Hedewald
 P.D.N.


Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 4 1/4 corner common to Sections 8 & 9
 4" CIM in Mon. Box
 Ottawa County Remonumentation Nail & Tag in W. side P.P. N 12° W 162.73'
 Ottawa County Remonumentation Nail & Tag in SE side P.P. S 36° W 54.78'
 Ottawa County Remonumentation Nail & Tag in SW side P.P. S 65° E 76.63'
 Ottawa County Remonumentation Nail & Tag in SE side 12" Pine N 65° E 40.22'

Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 18987

Date 10/18/1995



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

LCRC Liber 3, Page 200
November 15, 1977
Iron Pipe in Mon Box
Nail in face of 9" Pine NE 51.50
Nail in face of P.P. ESE 78.00
Nail in face of 10" Pine SW 54.20

LCRC Liber 4, Page 254
December 3, 1981
Fd. Iron Pipe, Set CIM
P.P. SE 76.54'
12" Pine East 37.47'
11" Pine SE 67.23'
P.P. SW 54.26'

* 11.00 CORNER