

1933

Ottawa County Remonumentation

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 15 AM 9:30

For corners in

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In: Robinson Township	Corner Code #: E-5
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>E-5</u>
	T _____ R _____	<u>N.W. Corner</u>
	T _____ R _____	<u>Section 16</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Carl P. Englert Jr.

I, _____, in a field survey on November 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-5 L.C.R.C. Liber 1, Page 825, 1/9/73
Fd. 1" pipe in Mon. Box
E.N.E. 52.4' T.P.
S.E. St. Sign 36.89'
S.W. 30" Oak 53.30'
N.E. 30" Oak 67.6'

L.C.R.C. Liber & Page, 3/15/89
Fd. Iron Pipe, Sec. C.I.M.
Nail in S.E. face 24" Oak, NW 67.0
P.K. Nail in Ne Face P.P. NW
109.48'
Nail in face 24" Oak SW 53.95'
NW face of St. Sign SE 36.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5
Found # Harrison in Mon. Box
and accepted as a careful and
fithful perpetuation of the
position of the original corner.

Found 28" Oak SW 54+
28" Oak NE 67+
P.K. Nail in P.P. NW 109.48'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 3" Harrison Cast Iron Monument in Mon.Box
O.C. Remon. Tag & Nail in SE side 28" Oak S. 38 degrees W. 54.46'
O.C. Remon. Tag & Nail in NE side P.P. N. 40 degrees W. 109.37'
O.C. Remon. Tag & Nail in SW side 28" Oak N. 33 degrees E. 66.96'
O.C. Remon. Tag & Nail in SW side P.P. S. 66 degrees E. 167.31'
(E.D.M.)

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date December 3, 1993

