

FEB 24 2000

RECORDED

OTTAWA COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 DEC -2 PM 1:13

SECTION

Larry [Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

OTTAWA
(County)

Located In: ROBINSON
(Township)

Corner Code #E-8

1. Public Land Survey

T 7N R R15W

E-8

T _____ R _____

West 1/4 Corner

T _____ R _____

Section 21

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													1
4	7			8			9			10			11
5													12
6	10			17			16			15			14
7													13
8	19			20			21			22			23
9													24
10	30			29			28			27			26
11													25
12	31			32			33			34			35
13													36

I, Robert E. Lemke, surveyor, in a field survey on September 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8

FOUND BROKEN CAST IRON MONUMENT IN MONUMENT BOX 7" BELOW THE TOP OF THE MONUMENT BOX. THE MONUMENT IS ON THE PHYSICAL CENTERLINE OF RICH STREET AND 1.5' WEST OF THE PHYSICAL CENTERLINE OF 128TH AVENUE.

38" MAPLE N.W. 82'

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8

CAST IRON MONUMENT IN MONUMENT BOX 7" BELOW THE TOP OF THE MONUMENT BOX.

SET NAIL WITH OTTAWA COUNTY REMON. TAG ON EAST SIDE OF 38" MAPLE 2.5' ABOVE GROUND.
SET NAIL WITH OTTAWA COUNTY REMON. TAG ON SOUTH SIDE OF WOOD POWER POLE 3' ABOVE GROUND.
CENTER OF STOP SIGN POST AT GROUND GRADE
SET NAIL WITH OTTAWA COUNTY REMON. TAG ON NORTH SIDE OF 8" MAPLE 2.5' ABOVE GROUND.
CENTER OF STOP SIGN POST AT GROUND GRADE

N. 30° W.	82.17'
N. 80° W.	60.70'
S. 45° W.	50.96'
S. 60° E.	64.91'
N. 45° E.	50.26'

Signed by Robert E. Lemke

For SDI CONSULTANTS, LTD

Date 11-15-1999

Surveyor's Michigan License No. 40160



SEE BACK

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
JAN. 28, 1971 REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

RECEIVED 11/15/99
ADJ

\$11.00 CORNER
Receipt #64945

FEB 24 2000

SECTION

OTTAWA COUNTY
ROBINSON TOWNSHIP
TOWN 7 NORTH, RANGE 15 WEST

E-8

A. Description of original monument and accessories and/or subsequent restoration

-G.L.O.

NORTH BETWEEN SECTIONS 20 & 21
40.00 SET 1/2 MILE POST
10" TAMK S. 81° E. 7 LINKS
10" TAMK N. 46° W. 44 LINKS
MAY 1832 (CALVIN BRITAIN)

-OTTAWA COUNTY ROAD COMMISSION NOTES

FOUND IRON PIPE (J.P.C. 1967)
14" BIRCH N.W. 49.05'
12" APPLE N.W. 56.40'
QUAD MAPLE N.W. 69.50'
ST. SIGN S.E. 38.80'
10" PINE S.E. 53.93'

-JOHN CLAPP, RECORDED L.C.R.C., LIBER 1 PAGE 587-588 RECORDED: 8-21-1972

SET CAST IRON MONUMENT

36" MAPLE	N.W.	81.25'
CL END ROAD CULVERT	N.E.	34.10'
CL END ROAD CULVERT	S.E.	34.75'
CL STREET SIGN	S.E.	40.65'
CL END ROAD CULVERT	S.W.	66.70'

-RECORDED CORNER NUMBERING CODE DIAGRAM, LIBER 1 PAGE 588

E-8 TO F-8 = N86°45'19"W 2607.56'
E-8 TO E-7 = DUE NORTH 2641.92'
E-8 TO E-9 = S01°05'10"W 2689.16'