

# SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:50

For corners **COMMISSION**

*Phyllis Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In: Robinson Twp.	Corner Code #/
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>E-9</u>
	T _____ R _____	<u>NE Corner</u>
	T _____ R _____	<u>Section 29</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert, in a field survey on December 05, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-9 corner common to Sections 20, 21, 28 & 29  
Original Gov't corner set May, 1832  
by Calvin Britain, D.S.

Set Corner  
Pine 3" N86°W 2.37 Chains  
Tamarack 3" S88°E 1.43 Chains

LCRC Liber 4, Page 281 (12/28/81)  
Set CIM  
P.P. S.E. 74.97'  
P.P. S.W. 83.73'  
Iron W. 33.00'  
12" Poplar N.W. 57.87'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 corner common to Sections 20, 21, 28 & 29

Found 4" Harrison C.I.M. with Broken top 3'+/- W. of Road E, 5" Deep  
Found P.P. S.E. 74.97'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 corner common to Sections 20, 21, 28 & 29

4" Harrison Cast Iron Mon. with Broken Top  
O.C. Remon. Tag & Nail in S.W. side P.P. S25°E 74.91'  
O.C. Remon. Tag & Nail in N.W. side P.P. S37°W 85.40'  
O.C. Remon. Tag & Nail in S.W. side 20" Ash N51°W 122.02'  
O.C. Remon. Tag & Nail in N.W. side 20" Ash N56°E 132.67'  
E Pavement M-45 North 114.40'+/-

Signed by Carl P. Englert Date 12/7/94  
Surveyor's Michigan License No. 10987

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

