

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:36

Robert R. Robinson
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

corners in

<u>Ottawa</u> (County)	Located In: <u>Robinson Twp</u>	Corner Code # <u>E-10</u>
Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>E 1/4 Corner</u>
	T _____ R _____	<u>Section 29</u>
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Carl P. Englert in a field survey on March 18, 19 94, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

E-10 1/4 corner common to Sections 28 and 29.
 Original gov't corner set May 1832 by Calvin Britain D.S.
 Set Post Pine 10" S88°W 3.09 chains Do 6" S88°E 1.20 chains
 L.C.R.C. Liber 2, Page 37
 P.P. N.W. 73.12'
 Centerline Stop Sign S.E. 44.38'
 8" Pine S.E. 52.83'
 P.P. S.E. 42.37'
 Guy Pole S.W. 36.50'
 14" Poplar W.N.W. 68.57'
 Fd. "T" Iron and Iron Pipe, Set C.I.M.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:


E-10 1/4 corner common to Sections 28 and 29.
 Found 4" Harrison Cast Iron Mon.
 Found P.P. N.W. 73.12'
 Found Centerline St. Sign S.E. 44.38'

Accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 11/21/94
Frederic P. Nedewell

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 1/4 corner common to Sections 28 and 29.
 4" Harrison C.I.M. 3" Deep, 3' +/- W. of the N & S Road Centerline
 O.C. Remon. Tag & Nail in S.W. side P.P. S. 53°E 333.27'
 O.C. Remon. Tag & Nail in E. side P.P. S. 13°W 198.48'
 O.C. Remon. Tag & Nail in S. side 26" Maple N. 80°W 171.33'
 O.C. Remon. Tag & Nail in N.E. side P.P. N. 39°W 73.58'



Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 18987

Date 11/17/94