

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:50

Phyllis Chittman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County) Located In: Robinson Twp. Corner Code ##

1. Public Land Survey T 7N R 15W E-11
T R SE corner
T R Section 29
T R _____
T R _____

2. Property Controlling S T R _____
in Section S T R _____

3. Miscellaneous S T R _____
Property in Sec. S T R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11 corner common to Sections 28, 29, 32 & 33
Original Gov't corner set May, 1832
by Calvin Britain D.S.

LCRC Liber 2, Page 35 (1/23/73)
Set CIM in place of iron pipe
8" Poplar ENE 29.22'
P.P. SSE 117.20'
P.P. WNW 43.15'
S. 55' to fence running east

Set Corner
Tamarak 3" S75°E 8 Links
Tamarak 3" S69°W 21 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 corner common to Sections 28, 29, 32 & 33

Found 4" Harrison CIM in Road $\frac{1}{2}$ 5" Deep (Broken Top)
Found P.P. SSE 117.20'
Found P.P. WNW 43.15'

PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Harvey D. Medeiros

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 corner common to Sections 28, 29, 32 & 33

4" Harrison Cast Iron Mon. with top broken off
O.C. Remon. Tag & Nail in N. side 6" Aspen S85°E 35.30'
O.C. Remon. Tag & Nail in E. side 15" Tw. Cherry N20°W 94.35'
O.C. Remon. Tag & Nail in W. side P.P. S18°E 117.51'
O.C. Remon. Tag & Nail in S. side P.P. N79°W 43.59'

Signed by

Carl P. Englert

Date

12/12/94

Surveyor's Michigan License No.

18987



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983