

**SURVEY &
REMONUMENTATION**

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Robinson Twp

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 7 N R 15 W	F - 3
	T R	N 1/4 corner
	T R	Section 9
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED

95 NOV 29 PM 1:48

Robert A. Anderson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3						9							
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl P. Englert, Jr., in a field survey on October 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F - 3 1/4 corner common to Sections 4 & 9.	LCRC Liber 3, Page 375
Original Corner Set May, 1832	November 1, 1978
by Calvin Britain	Fd Angle Iron, Set CIM
Set 1/2 Sec. Post on True Line	8" Tw Poplar NW 24.36'
W. Oak 20" S 51° E 10 Links	10" Oak NE 21.06'
Pine 20" N 65° W 36 Links	10" Oak SE 43.29'
	16" Oak SW 54.90'

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F - 3 1/4 corner common to Sections 4 & 9.
Found 4" CIM on N. edge of Gravel Road 1' ± deep
Found 14" Oak NE 21.06'
Found 14" Oak SE 43.29'
Found 12" Aspen NW 24.31'
Found 19" Oak SW 54.9±

PA. 345 OTTAWA COUNTY
PEER APPROVED 11-20-95


Maday P. Nedewell
YDN

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F - 3 1/4 corner common to Sections 4 & 9
4" CIM
Ottawa County Remonumentation Tag and Nail in SW side 15" Oak S 21° E 43.35'
Ottawa County Remonumentation Tag and Nail in SE side 18" Oak S 52° W 65.06'
Ottawa County Remonumentation Tag and Nail in E. side 12" Aspen N 33° W 24.24'
Ottawa County Remonumentation Tag and Nail in N. side 14" Oak N 55° E 21.08'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18907



10/17/95 1995

F - 3 Section 9 - 7 - 15

Liber 4, Page 156 March 22, 1981

Sq. Spike in W'ly side 14" Oak SSE 43.31'

Sq. Spike in N'ly side 14" Oak ESE 21.10'

Sq. Spike in E'ly side 12" Poplar NW 24.31'

\$ 11.00 CORNER