

Ottawa County Remonumentation
COMMISSION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:30

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

Robinson Township

- 1. Public Land Survey T 7N R 15W F-7
T _____ R _____ S 1/2 Corner
T _____ R _____ Section 16
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Carl P. Englert Jr.

November 10, 1993

I, _____, in a field survey on _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- F-7 L.C.R.C., Liber 2, Page 587 (9-20-1974) Fd. Iron pipe St. Sign, SE 30.55' 24" Oak, SE 29.35' 10" Cherry, SW 40.45' 18" Pine, SW 63.85' 10" Pine, NW 33.35' Tw. 18" Oak, NE 58.23'
- L.C.R.C., liber 3. Page 296 (9-18-1978) Fd. pinched iron pipe, Set C.I.M. 20" Oak, NNE 87.78' 12" Oak, SE 52.67' 18" Oak, SSW 73.39'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-7 Found 4" Harrison 2'± South of centerline of gravel road, 3" deep and accepted as a careful and faithful perpetuation of the position of the original corner.
- Found 13" Oak, SE 53'± 28" Oak, SE 29.5' ± 29" Oak, NE 58.23'± (nail in face)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-7 4" Harrison cast iron monument
- O.C. Remon. Tag & Nail in W side 36" Oak, S 17 degrees E 29.69'
- O.C. Remon. Tag & Nail in NE side 13" Oak, S 60 degrees E 53.40'
- O.C. Remon. Tag & Nail in SE side 28" Oak, N 60 degrees E 59.84'
- O.C. Remon. Tag & Nail in NE side P.P., N 60 degrees W 42.13'
- O.C. Remon. Tag & Nail in NE side 8" Pine, N 33 degrees W 61.59'

(E.D.M.)

Signed by Carl P. Englert Jr. Date December 3, 1993
Surveyor's Michigan License No. 18987