

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 DEC -2 PH 1:13

SECTION

For corners in

OTTAWA
(County)

Located In: ROBINSON
(Township)

Corner Code # F-11

Darryl Schell
REGISTER OF DEEDS
OTTAWA COUNTY, MI

1. Public Land Survey	T	<u>7N</u>	<u>R15W</u>	<u>F-11</u>
	T		R	North 1/4 Corner
	T		R	Section 33
	T		R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	13			17		16		15		14		12	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Robert E. Lemke, surveyor, in a field survey on September 9, 1999 do hereby state that underequirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED 11/15/99
YD7



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11

FOUND BROKEN CAST IRON MONUMENT 13" BELOW GROUND GRADE.

FOUND 8" DIAMETER AND 5' HIGH WOOD FENCE POST ALONG THE WEST SIDE OF CAST IRON MONUMENT.

CAST IRON MONUMENT IS ON AN OCCUPATION LINE BETWEEN A GOLF COURSE DEVELOPMENT TO THE SOUTH AND A NURSERY TO THE NORTH.

MEASURED 2655.56' BETWEEN F-11 AND E-11. 1988 SURVEY RECORDED LIBER 7 PAGE 341 SHOWS DISTANCE OF 2656.44'. ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11

FOUND BROKEN CAST IRON MONUMENT 13" BELOW GROUND GRADE

SET 1/2 " IRON BAR 18" LONG WITH CAP "SDI 40160"
SET 1/2 " IRON BAR 18" LONG WITH CAP "SDI 40160"
SET 1/2 " IRON BAR 18" LONG WITH CAP "SDI 40160"
SET 1/2 " IRON BAR 18" LONG WITH CAP "SDI 40160"
DISTANCE FROM F-11 TO E-11 IS

N. 15° W. 44.43'
S. 45° W. 67.64'
S. 5° E. 18.14'
S. 45° E. 48.24'
2655.56'

Signed by Robert E. Lemke

Date 11-15-99

For SDI CONSULTANTS, LTD

Surveyor's Michigan License No. 40160

411.00 CORNER
Receipt #64945

SEE BACK

FEB 24 2000

SECTION

OTTAWA COUNTY
ROBINSON TOWNSHIP
TOWN 7 NORTH, RANGE 15 WEST

F-11

A. Description of original monument and accessories and/or subsequent restoration

-G.L.O.

EAST ON RANDOM BETWEEN SEC'S 28 & 33
40.00 TEMP. ¼ SEC. POST
78.95 INTERSECT LINE 19 LINKS NORTH OF POST
CORRECTED WEST
39.47 ¼ SEC POST ON TRUE LINE
18" HEMLOCK S. 83° E 5 LINKS
10" W. ASH S. 70° W. 27 LINKS
MAY 1832 (CALVIN BRITAIN)

-THOMAS JOINER, RECORDED L.C.R.C. LIBER 5 PAGE 55 ON: 5-17-1983

FOUND IRON BAR FROM PREVIOUS SURVEY

SET CAST IRON MONUMENT

6" ASPEN	NNW	67.00'
TW. PEPPERIDGE	WNW	35.74'
MAPLE CLUMP	WNW	70.62'
6" PEPPERIDGE.	NW	77.60'

-DONALD SCHIELE, RECORDED BOUNDARY SURVEY, LIBER 7 PAGE 341 SURVEY DATED 7-15-1988

F-11 WEST TO E-11 = N89°20'45"W 2656.44'

FOUND CAST IRON MONUMENT

18" TWIN PEPPERIDGE	WNW	35.74'
33" MAPLE CLUMP	WNW	70.64'
7" PEPPERIDGE	NW	77.62'
7" ASPEN	NNW	66.93'