

SURVEY &
REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Robinson Twp.

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7</u> N R <u>15</u> W	<u>G - 4</u>
	T _____ R _____	<u>W 1/4 Corner</u>
	T _____ R _____	<u>Section 10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

95 NOV 29 PM 1:47

Polycarpus Chalkman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert, Jr., in a field survey on October 16, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G - 4 1/4 Corner common to Sections 9 & 10	LCRC Liber 1, Page 629
Original Corner set by Calvin Britain	Fd. Angle Iron
May, 1832.	NW Cor. Fence Post 33.62'
Set 1/2 Mile Post	SW 20" Sycamore 36.76'
Blk Ash 12" N 55° W 30 Links	W. P.P. 63.67'
Blk Ash 12" N 64° E 37 Links	

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G - 4 1/4 Corner common to Sections 9 & 10
Found 4" CIM in Mon Box 1.5'± E. of CL Asphalt Road
Found P.P. W. 63.67'
Found 30" Sycamore SW 36.76± (no nail)
W. P.P. 64.09'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11-20-95

Madison D. Nedewell

CPJ

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 4 1/4 Corner common to Sections 9 & 10
4" CIM in Mon Box.
Ottawa County Remonumentation Nail and Tag in SE Side of 30" Sycamore S 47° W 37.67'
Ottawa County Remonumentation Nail and Tag in S. side P.P. S 90° W 64.09'
Ottawa County Remonumentation Nail and Tag in S. side 7" Oak N 56° E 57.57'
Ottawa County Remonumentation Nail and Tag in N. side 12" Oak S 58° E 61.32'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 10/17/1995



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983

LCRC Liber 4, Page 156 March 22, 1981

Found Angle Iron

Sq Spike in NW Side 26" Sycamore SW 37.72'

Sq Spike in NW Side 8" Tw Ash NE 27.97'

P.K. in S. Side P.P. W. 64.11'

LCRC Liber 4, Page 253 December 3, 1981

Fd Angle Iron over fence post

32" Sycamore SW 37.72'

P.P. West 64.12'

5" Oak ENE 44.45'

12" Poplar NE 58.07'

\$ 11.00 CORNER