

1898

Ottawa County Remonumentation

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 15 AM 9:30

For corners in

Dorothy Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In:	Corner Code #
	Robinson Township	
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>G-5</u>
	T _____ R _____	<u>N.E. Corner</u>
	T _____ R _____	<u>Section 16</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Carl P. Englert Jr.

I, _____, in a field survey on November 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| G-5 L.C.R.C. Liber 1, Page 381, 5/11/72
Fd. 1" pipe
Nail in face of 12" Maple N.E. 70.50'
Nail in face of T.P. N.E. 53.63'
Nail in face of 18" Oak N.E. 122.97'
Nail in face of T.P. S.E. 77.13'
Nail in face of P.P. S.E. 71.04'
Nail in face of 15" Oak W.N.W. 170.04 | L.C.R.C. Liber 4, Page 253
Fd. 1" pipe, Set C.I.M.
T.P. N.E. 53.65'
Tw. 10" Poplar W.N.W. 59.97'
P.P. S.E. 71.58'
T.P. S.E. 77.10' |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|---|---|
| G-5
Found 4" Harrison in Mon. Box
and accepted as a careful and faithful perpetuation of the position of the original corner. | Fd. Tw. 10" Poplar W.N.W. 59.95'
P.P. S.E. 71.58'
18" Oak N.E. 122.9+ |
|---|---|



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-5 4" Harrison Cast Iron Monument in Mon. Box
O.C. Remon. Tag & Nail in S.E. side 24" Oak N. 45 degrees E. 101.70'
O.C. Remon. Tag & Nail in E. side P.P. N. 11 degrees W. 163.47'
O.C. Remon. Tag & Nail in N. side 15" Tw. Aspen N. 66 degrees E. 59.36'
O.C. Remon. Tag & Nail in W. side Litepole S. 5 degrees E. 40.93'
O.C. Remon. Tag & Nail in E. side P.P. S. 23 degrees E. 71.49'
(E.D.M.)

Signed by Carl P. Englert Jr. Date December 3, 1993
Surveyor's Michigan License No. 18987