

Ottawa County Remonumentation

RECORDED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 15 AM 9:30

*Polycia R. Kallman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
	<u>Robinson Township</u>	
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>G-6</u>
	T _____ R _____	<u>E. 1/4 Corner</u>
	T _____ R _____	<u>Section 16</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl P. Englert Jr., in a field survey on August 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-6 L.C.R.C. Liber 3, Page 181, 9/16/77  
 Fd. 1" Iron in Mon. Box  
 W. 24" Oak 31.14'  
 S.W. P.K. in Guy P. 46.56'  
 E. Guy Pole 98.59'  
 S.E. 12" Poplar 88.19'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 Found 3" Harrison in Mon. Box 1.0' ± West of C/L 120th Ave.  
 and accepted as a careful and Fd. W. 24" Oak 31.14'  
 faithful perpetuation of the S.W. P.K. in T.P. 46.56'  
 position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 3" Harrison Cast iron monument in Mon. Box.  
 O.C. Remon. Tag & Nail in E. side 24" Aspen 5.25 degrees E. 124.00'  
 O.C. Remon. Tag & Nail in N.W. side T.P. 5.42 degrees W. 46.45'  
 O.C. Remon. Tag & Nail in N. side 30" Oak N. 82 degrees W. 31.02'  
 O.C. Remon. Tag & Nail in S.W. side 7" Birch N. 46 degrees W. 45.39'  
 (E.D.M.)

Signed by Carl P. Englert Jr. Date December 3, 1993  
 Surveyor's Michigan License No. 18987

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS (REVISED MAY 1989)

