

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> (County)	Located in: Robinson Twp	Corner Code # G-8
1. Public Land Survey	T <u>7</u> N R <u>15</u> W	<u>W 1/4</u> corner
	T ___ R ___	<u>Section 22</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED

96 NOV 14 AM 11:20

Elizabeth Redmond
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, in a field survey on 9/10, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-8 1/4 corner common to Sections 21 and 22	LCRC Liber 1, Page 129
G.L.O. May, 1832 Calvin Britain	Set R.R. Spike in C BT.
Set 1/2 mile post	P.P. N40°W 99.30'
7" Pine N67°E 86 links	4" W. Pine S42°W 85.00'
10" Tamarack N15°W 65 links	St. Sign N72°E 27.50'
	2664.50 S. of NE. cor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 1/4 corner common to Sections 21 & 22
Found R.R. Spike in Mon. Box
Found P.P. N40°W 99.30'
Found St. Sign 27.5'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 9-16-96
C.P. Englert Jr.

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 1/4 corner common to Sections 21 and 22
Replaced R.R. Spike with 3/4"x2' Iron bar with OC Remon Cap in Mon. Box

O.C. Remon tag & nail in N.W. side 10" Poplar	N40°W 75.07'
O.C. Remon tag & nail in S. side 5" Cherry	S70°E 51.23'
O.C. Remon tag & nail in S. side P.P.	N63°W 66.32'
O.C. Remon tag & nail in N.E. side P.P.	N36°W 99.46'

Corner on C Road N., S. & W. and on occupation line East



Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date Sept. 11, 1996