

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 15 AM 9:29

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
	<u>Robinson Township</u>	
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>G-11</u>
	T _____ R _____	<u>NW corner</u>
	T _____ R _____	<u>Section 34</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Edyline Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Carl P. Englert Jr.

I, \_\_\_\_\_, in a field survey on July 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- |                   |                                        |                                     |
|-------------------|----------------------------------------|-------------------------------------|
| G-11              | L.C.R.C. Liber 2, Page 415, (11-30-73) | L.C.R.C. Liber 6, Page 58, (10-12-9 |
| Found 1" iron bar | NE 53.50 12" Pine                      | Found 1" iron bar, set C.I.M.       |
| NE 61.42 P.P.     | SE 46.56 St. sign                      | 6" Maple SW 42.90'                  |
|                   |                                        | P.P. NE 61.46'                      |
|                   |                                        | P.P. SE 57.02'                      |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-11  
Found 4" Harrison Monument in monument box and accepted as a careful and faithful perpetuation of the position of the original corner. 6" Maple SW 42.90'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-11 Set O.C. Remon. Cap over Harrison C.I.M. in Mon. box  
 O.C. Remon Tag & Nail in NW side P.P. N40 degrees E 63.07'  
 O.C. Remon Tag & Nail in N side 15" Pine N 75 degrees E 86.59'  
 O.C. Remon Tag & Nail in SE side 6" Maple S 40 degrees W 42.93'  
 O.C. Remon Tag & Nail in SW side P.P. S 45 degrees E 57.29'  
 O.C. Remon Tag & Nail in NE side 9" Oak N 44 degrees W 81.13'

Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

Date December 3, 1993

