

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:52

For corners in

<u>Ottawa</u> (County)	Located In: <u>Robinson Twp.</u>	Corner Code # <u>H-5</u>
1. Public Land Survey	T <u>7</u> R <u>15</u>	<u>S 1/4 Corner</u> <u>Section 10</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, in a field survey on December 01, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-5 1/4 corner common to Sections 10 & 15
Original Gov't corner set May, 1832
by Calvin Britain D.S.

LCRC Liber 4, Page 255 (12/3/81)
H-5
Set Cast Iron Monument
Power Pole NE 60.42
24" Oak NW 54.47
10" Sassafras South 39.67
Power Pole SW 129.58

Set Post
Maple 18" N50°E 27 Links
Beech 18" S55°W 23 Links

(See Back of Page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-5 1/4 corner common to Sections 10 & 15

Found 3" Harrison Cast Iron Monument in Mon. Box, 0.5' North of E of Road
6" Deep

Found Power Pole NE 60.42'
Found 24" Oak NW 54.47'
Found 10" Sassafras S 39.67'
Found Power Pole SW 129.58'

PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Maday D. Wederwald

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-5 1/4 corner common to Sections 10 & 15

3" Harrison Cast Iron Mon. in Mon. Box
O.C. Remon. Tag & Nail in E. side Power Pole N29°E 60.41'
O.C. Remon. Tag & Nail in E. side 24" Oak N22°W 54.46'
O.C. Remon. Tag & Nail in W. side 13" Sassafras S 0°W 39.67'
O.C. Remon. Tag & Nail in S.E. side Power Pole S62°W 129.72'



Signed by Carl P. Englert Date 12/5/94
Surveyor's Michigan License No. 18987

LCRC Liber 3, Page 335 (2/10/79)

H-5

(Found) 1" Pipe

N.N.E.	53.40'	8" Aspen
N.W.	54.73'	18" Oak
S.	39.67'	10" Sassafras

RECORDED
INDEXED
FEB 10 1979