

**SURVEY &
REMONUMENTATION**

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:52

COMMISSION

For corners in

Ottawa
(County)

Located in:
Robinson Twp.

Corner Code #

- | | | |
|---------------------------------------|------------------------|---------------------|
| 1. Public Land Survey | T <u>7</u> R <u>15</u> | <u>H-7</u> |
| | T ___ R ___ | <u>S 1/4 corner</u> |
| | T ___ R ___ | <u>Section 15</u> |
| | T ___ R ___ | _____ |
| 2. Property Controlling
in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Carl P. Englert, in a field survey on December 01, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-7 1/4 corner common to Sections 15 & 22
Original Gov't corner set May 1832
by Calvin Britain, D.S.

LCRC Liber 4, Page 161, (1/5/81)
H-7
Set Cast Iron Monument
Power Pole North 60.23
32" Oak NE 98.25
12" Cherry SE 44.51

Set Post
Maple 20" N4°E 11 Links
W. Oak 24" S16°E 41 Links

(See Back of Page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 1/4 corner common to Sections 15 & 22

Found 3" Harrison Cast Iron Mon. with broken top 5.5' South of $\frac{1}{2}$ of Road 1" deep
Found 36" Oak N.E. 98.08'
Found 10" Cherry S.E. 44.59'

PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Madop D. Hedewell

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 1/4 corner common to Sections 15 & 22

3" Harrison Cast Iron Mon. (Broken Top)

O.C. Remon. Tag & Nail in E. side Power Pole	N10°W	61.03'
O.C. Remon. Tag & Nail in S. side 36" Oak	N72°E	97.99'
O.C. Remon. Tag & Nail in N.W. side 14" Cherry	S62°E	44.98'
O.C. Remon. Tag & Nail in S.E. side 8" Red Pine	S38°W	38.60'

Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 12/5/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JANUARY, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LCRC Liber 2, Page 579, (6/27/74)
H-7
Found Angle Iron in 2" Pipe
10" Oak . NNW 32.50'
12" Cherry ESE 44.60'

LCRC Liber 2, Page 793, (7/24/75)
H-7
Found 2" Pipe with Angle Iron
Drove in Center
NW 12" Oak 27.72'
NE 36" Oak 98.08'
SE 10" Cherry 44.59'

0000 # 0000
0000 # 0000
0000 # 0000
0000 # 0000
0000 # 0000