

REGISTERED  
 1898  
 COUNTY

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:28

*Elizabeth Ballman*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In: Robinson Township	Corner Code # H-11
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>N 1/4</u> Corner <u>Section 34</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Carl P. Englert Jr.

I, \_\_\_\_\_, in a field survey on July 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-11  
 L.C.R.C. Liber 2, Page 415, 11/30/93  
 Fd. 5/8" Rod  
 SW 31.08' Clump of Maples  
 NW 42.07' 14" Oak  
 WNW 60.73' 28" Oak


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11  
 Found 5/8" Re-bar 3' Deep and accepted as a careful and faithful perpetuation of the position of the original corner.

No Witts found  
 corner is on line between  
 NE & NW corners & Distances OK.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 Set 3' lone 3/4" Iron bar with O.C. Remon. Cap.  
 O.C. Remon. Tag & Nail in SE side 10" Cherry S 9 degrees E 60.48'  
 O.C. Remon. Tag & Nail in NW side 10" Maple S 14 degrees W 38.32'  
 O.C. Remon. Tag & Nail in NW side 10" Aspen S 52 degrees W 58.91'  
 Center of buried Cable Marker N 3 degrees 39.48'  
 NE Cor. Sec. 34 East 2628.72'  
 NW Cor. Sec. 34 West 2635.27'  
 (E.D.M.)



Signed by Carl P. Englert Jr.  
 Surveyor's Michigan License No. \_\_\_\_\_

Date December 3, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983