

SURVEY & REMONUMENTATION

JUN 28 1999

RECORDED

98 NOV 11 PM 1:26

SECTION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Samuel H. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Robinson Twp.

Ottawa

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------------------|-----------|
| 1. Public Land Survey | T <u>7</u> N R <u>15</u> W | I-1 |
| | T ___ R ___ | NW corner |
| | T ___ R ___ | Section 2 |
| | T ___ R ___ | |
| 2. Property Controlling in Section | S ___ T ___ R ___ | |
| | S ___ T ___ R ___ | |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | |
| | S ___ T ___ R ___ | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, Jr. in a field survey on 10/16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3			2		1	
3													
4	7		8		9		10			11		12	
5													
6	18		17		16		15			14		13	
7													
8	19		20		21		22			23		24	
9													
10	30		29		28		27			26		25	
11													
12	31		32		33		34			35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-1 Corner common to Sections 2 and 3, T7N, R15W
G.L.O. 1832 by Noah Brookfield
North boundary 60 Links E of Post
W. Oak 12" S 11° W 18 Links
Pine 20" S 15° E 22 Links

Set corner to Sections 2 and 3
E.H. Peck County Surveyor 1899
Found Stone

This corner shown on Survey Notes by Excel Eng. Oct., 1988

See other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- I-1 Found 4" Cast Iron Monument at grade
Found SW corner of Section 35, T8N, R15W WEST ~~39.80~~ 39.80'

DA. OAS. OTTAWA COUNTY
PEER APPROVED 10/19/98
[Signature]

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-1 Corner common to Sections 2 and 3, T7N, R15W
4" Harrison Cast Iron Monument on Town line
O.C. Remon Tag & Nail in NE side 5" Oak N 66° W 108.21'
O.C. Remon Tag & Nail in NE side 7" Oak S 67° W 95.55'
O.C. Remon Tag & Nail in NE side 8" Cherry S 10° E 81.89'
O.C. Remon Tag & Nail in N side 4" Oak S 57° E 72.24'
O.C. Remon Tag & Nail in SE side 4" Oak N 16° E 73.35'
SW corner Section 35, T8N, R15W West 39.80'



Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 10/17/1998

\$11.00 CORNER
Receipt #19293

\$2.00 PHOTO
Receipt #19293

SURVEY &
REMONUMENTATION

JUN 28 1999

SECTION

