

APR 05 1996

OTTAWA COUNTY REMONUMENTATION
COMMISSIONLAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Robinson Twp.

<u>Ottawa</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>7</u> N R <u>15</u> W	<u>I - 3</u>
	T _____ R _____	<u>NW Corner</u>
	T _____ R _____	<u>Section 11</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

95 NOV 29 PM 1:48

Richard Kellerman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3								●				
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl P. Englert, Jr., in a field survey on October 16, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I - 3 Corner common to Sections 2, 3, 10, & 11 Original Corner set in May 1832 by Calvin Britain Set Corner Blk Ash 10" S 19° E 17 Links Beech 15" N 41° W 36 Links	LCRC Liber 1, Page 43 June 26, 1971 Fd 3/4" Steel Bar CL S end Culvert SW 26.3' CL N end Culvert NW 25.00' 10" Quad Maple NW 65.58' 8" Poplar NE 26.3 8" Maple NNW 48.14' 5" Ash S 39.83'
--	---

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 3 Corner common to Sections 2, 3, 10, & 11
Found 4" CIM With Broken Top
Found 8" Ash S 39.93'
Found 10" Quad Maple NW 65.58 (34" Maple)
Found P.P. SW 59.25'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11-20-95

Richard P. Redwood
RDN

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 3 Corner Common to Sections 2, 3, 10, & 11.
4" CIM in Road centerline with Broken top
Ottawa County Remonumentation Tag and Nail in S. side 34" Maple N 69° W 67.14'
Ottawa County Remonumentation Tag and Nail in SE side P.P. S 60° W 59.27'
Ottawa County Remonumentation Tag and Nail in N. side P.P. S 77° E 111.73'
Cut Cross in Concrete Culvert S. End S 41° W 29.40'
Cut Cross in Concrete Culvert N. End N 51° W 27.58'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 10/17/1995



Robinson Township T 7 N, R 15 W
I - 3 Liber 3, Page 349
Fd 3/4" Rod
NNW 8" Maple 48.14'
N. End Culvert 25.00'
S. 5" Ash 39.83'

I - 3 Liber 4, Page 141
Fd Iron Bar, Set CIM
P.P. SW 59.25'
10" Tree S. 42.63'
34" Maple NW 65.66'
10" Poplar NNE 29.60'

\$ 11.00 CORNER