

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:51

COMMISSION

For corners in

Phyllis Williams
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Ottawa (County) Located In: Robinson Twp. Corner Code #

1. Public Land Survey	T <u>7</u> R <u>15</u>	<u>I-6</u>
	T <u> </u> R <u> </u>	<u>East 1/4</u>
	T <u> </u> R <u> </u>	<u>Corner</u>
	T <u> </u> R <u> </u>	<u>Section 15</u>
2. Property Controlling In Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>		
5. Private Claims <u> </u>		

Register of Deeds Stamp & File Number

I, Carl P. Englert, in a field survey on December 01, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6 1/4 corner common to Sections 14 & 15
 Original gov't corner set May, 1832
 by Calvin Britain D.S.

LCRC Liber 4, Page 129, (12/4/80)
 I-6
 Found Cast Iron Monument
 Power Pole N.E. 55.70
 36" Oak S.E. 34.32
 14" Tw. Maple S.W. 38.45
 18" Maple W.S.W. 28.50

Set 1/2 mile post
 W. Oak 24" S29°E 38 Links
 W. Oak 20" N36°W 26 Links

(See Back of Page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 1/4 corner common to Sections 14 & 15

Found 3" Harrison Cast Iron Mon., 2' East of $\frac{1}{2}$ of Road, 2" deep
 Found Power Pole N.E. 55.70'
 Found 36" Oak S.E. 34.32'
 Found 14" Twin Maple S.W. 38.45'
 Found 18" Maple W.S.W. 28.50'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94


Hardy D. Nedrow

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 1/4 corner common to Sections 14 & 15

3" Harrison Cast Iron Mon.
 O.C. Remon. Tag & Nail in S.E. Side Power Pole N41°E 55.65'
 O.C. Remon. Tag & Nail in N. Side 36" Oak S46°E 35.51'
 O.C. Remon. Tag & Nail in S. Side Twin 14" Maple S43°W 39.84'
 O.C. Remon. Tag & Nail in S. Side 18" Maple S75°W 28.65'



Signed by Carl P. Englert Jr.

Date 12/5/94

Surveyor's Michigan License No. 18987

LCRC Liber 2, Page 793, (7/24/75)

I-6
 Found 1 1/4" Pipe
 N.E. Power Pole 55.54'
 S.E. 36" Oak 36.25'
 S.W. 18" Maple 28.77'

LCRC Liber 3, Page 172, (7/11/77)

I-6
 Power Pole N42°E 55.34
 10" R. Maple N21°W 67.42
 22" W. Oak S62°E 34.22
 20" Twin R Maple S44°W 38.42

230 #
 5.00
 150 #
 230 #