

**SURVEY & REMONUMENTATION**

DEC 16 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In: Robinson Township	Corner Code # I-8
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	East $\frac{1}{4}$ corner Section 22
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED  
96 NOV 14 AM 11:21  
*Regina Kullman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Carl P. Englert, in a field survey on 9/12, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-8 1/4 corner common to Sections 22 & 23  
G.L.O. May 1832 by Calvin Britain  
Set 1/2 mile Post  
Pine 6" S35°E 36 Links  
Pine 6" N5°W 6 Links  
  
See other side

LCRC Liber 2, Page 581  
September, 1974  
Found Iron Pipe  
30" B. Oak N.E. 64.24'  
24" B. Oak N.E. 109.45'  
P.P. S.E. 110.22'  
24" B. Oak S5°W 63.33'  
20" B. Oak S30°W 21.08'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


I-8 1/4 corner common to Sections 22 & 23  
Found Cast Iron Monument  
Found 10" Maple N. 55.15'  
Found 36" Oak N.E. 63.48'  
Found 24" Oak N.E. 109.45'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 9-16-96  
*C.P. Englert*

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8 1/4 corner common to Sections 22 & 23  
4" Harrison Cast Iron Monument 6" deep on East Bank of Ditch  
O.C. Remon tag & nail in N. side P.P. S67°E 110.36'  
O.C. Remon tag & nail in W. side 38" Oak N36°E 63.29'  
O.C. Remon tag & nail in W. side 15" Maple North 48.27'  
O.C. Remon tag & nail in S. side 24" Oak N69°W 77.03'  
O.C. Remon tag & nail in E. side 10" Maple S4°W 120.65'  
On  $\frac{1}{2}$  Ditch West and on Tree Line North



Signed by Carl P. Englert  
Surveyor's Michigan License No. 16387

Date 9/16/1996

DEC 16 1996

COMMISSION

I-8 E. 1/4 corner Section 22, Town 7 North, Range 15 West  
LCRC Liber 2, Page 789 July, 1975  
Found 3/4" pipe  
S.W. 21.03' 30" Oak  
N. 55.15' 10" Maple  
N.E. 63.48' 36" Oak

LCRC Liber 2, Page 745 February 1975  
Accessories Fit West 1/4 Corner of Section 22,  
Not the East 1/4 Corner

LCRC Liber 4, Page 37 March, 1980  
Found 3/4 inch pipe, Set Cast Iron Monument  
Existing Witnesses unchanged.