

SURVEY &  
REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Robinson Twp.

Ottawa

(County)

Located In:

Corner Code #

|                                    |   |       |      |       |
|------------------------------------|---|-------|------|-------|
|                                    |   | 7 N   | 15 W |       |
| 1. Public Land Survey              | T | _____ | R    | _____ |
|                                    | T | _____ | R    | _____ |
|                                    | T | _____ | R    | _____ |
|                                    | T | _____ | R    | _____ |
| 2. Property Controlling in Section | S | _____ | T    | _____ |
|                                    | S | _____ | T    | _____ |
| 3. Miscellaneous Property in Sec.  | S | _____ | T    | _____ |
|                                    | S | _____ | T    | _____ |

I - 10  
E 1/4 corner  
Section 27

RECORDED

95 NOV 29 PM 1:41

*Rhonda S. Holman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Carl P. Englert, Jr., in a field survey on October 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

|        |                                       |                        |
|--------|---------------------------------------|------------------------|
| I - 10 | 1/4 corner common to Sections 26 & 27 | LCRC Liber 2, Page 415 |
|        | Original corner set May 1832          | November 28, 1973      |
|        | by Calvin Britain D.S.                | Fd CIM                 |
|        | Set 1/2 mile post                     | NE P.P. 65.91'         |
|        | Pine 10" N 58° E 23 Links             | W. T.P. 37.79'         |
|        | Beech 6" S 40° W 9 Links              | SW 6" Pine 57.52'      |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 10 1/4 Corner common to Sections 26 & 27  
Found 4" CIM with top broken off 10" Deep in CL Intersection  
Found P.P. NE 65.91'  
Found 10" Pine SW 57.5'± (Dead and Bent over)

PA. 345 OTTAWA COUNTY

PEER APPROVED 11/20/95

Accepted as a careful and faithful perpetuation of the position of the original corner.

*Rhonda S. Holman*  
*YDN*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 10 1/4 corner common to Sections 26 & 27  
4" CIM  
Ottawa County Remonumentation tag and nail in SW side P.P. S 50° E 56.41'  
Ottawa County Remonumentation tag and nail in SW side Cutoff Tel. Pole N 50° W 44.84'  
Ottawa County Remonumentation tag and nail in NW side P.P. N 45° E 65.70'  
Ottawa County Remonumentation tag and nail in NW side 10" Pine S 40° W 46.76'

Signed by Carl P. Englert Jr.

Surveyor's Michigan License No. 18987

