

1993

Ottawa County Remonumentation

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 15 AM 9:29

For corners in

Robert A. Chalmers
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In:	Corner Code ##
	<u>Robinson Township</u>	
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>I-11</u>
	T _____ R _____	<u>NE corner</u>
	T _____ R _____	<u>Section 34</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Carl P. Englert Jr., in a field survey on July 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11
L.C.R.C. Liber 2, Page 415, (11-28-73)
NW T.P. 43.60
SW T.P. 36.17
SE St. Sign 38.42


L.C.R.C. Liber 4, Page 140, (12-10-
Fd. 3/4" pipe, Set C.I.M.
P.P. NE. 72.13
38" Oak SW 93.60
Street sign SE 38.49
T.P. NW 43.68

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11
Found 4" Harrison monument with broken top and accepted as a careful and faithful perpetuation of the position of the original corner. 38" Oak SW 93.60'
Street sign SE 38.49'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Replaced broken Harrison monument with 3' long, 3/4" Iron bar with O.C. Remon. Cap
O.C. Remon. Tag & Nail in NW side P.P. N 46 degrees E 46.89'
O.C. Remon. Tag & Nail in N side P.P. S 65 degrees E 71.28'
O.C. Remon. Tag & Nail in E side P.P. N 43 degrees W 45.90'
O.C. Remon, Tag & Nail in SE side 40" Oak S 67 degrees W 93.49'
O.C. Remon. Tag & Nail in SE side 28" Maple N 24 degrees W 79.99'
(EDM)



Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date December 3, 1993